

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-153-20546-00-00  
Spot: NENE Sec/Twnshp/Rge: 23-1S-35W  
4620 feet from S Section Line, 660 feet from E Section Line  
Lease Name: ROONEY Well #: 1  
County: RAWLINS Total Vertical Depth: 4378 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: 202 SOUTH ST. FRANCIS PO BOX 2757  
WICHITA, KS 67201

PROD Size: 4.5 feet: 4377 w/150 sxs cmt  
SURF Size: 8.625 feet: 336 w/250 sxs cmt

#142<sup>29</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/11/2004 9:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: GARY REH Company: GORE OIL COMPANY Phone: (308) 345-1597

Proposed Plugging Method: Ordered out 250 sxs Swift Multi-Density Cement with 600# hulls.  
TOC 3250'.  
LKC Perfs 3174' - 4276'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: NONE  
Date/Time Plugging Completed: 10/11/2004 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3100'.  
Swift Services pumped 50 sxs SMD with 400# hulls.  
Pulled tubing to 2100'. Swift Services pumped 50 sxs SMD.  
Pulled tubing to 1000'. Pumped 50 sxs SMD with 200# hulls - cement circulated.  
PTOH. Topped off casing with 12 sxs SMD - hole full.  
Hooked up to 8 5/8" and pumped 23 sxs SMD.  
Max. P.S.I. 200#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
4266	4276		
4224	4230		
4174	4182		

RECEIVED  
JAN 18 2005  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

*MD*

Signed Richard Williams  
(TECHNICIAN)

INVOICED

DATE 1-19-05


INV. NO. 2005061078

JAN 13 2005

44' MS  
OYAE

INDICED

ABRAXAS PETROLEUM CORPORATION REPLACEMENT CARD  
 P.O. BOX 17485 #1 ROONEY 23-1-35W  
 SAN ANTONIO, TX 78217 C NE NE  
 CONTR MURFIN DRILLING CTY RAWLINS  
 GEOL ROBERT DILTS FIELD CAHOJ WEST EXT  
 (1/4 S)  
 ELV 3161 KB SPD 5/9/84 CARD ISSUED 7/26/84 IP P 88 BO & 49 BWPD  
 3156 GL LKC 4174-4276 OA  
 API 15-153-20,546



SMP	Tops	Depth/Datum
ANH	3016 + 145	
B/ANH	3052 + 109	
TOP	3860 - 699	
OREAD	3954 - 793	
HEEB	4014 - 853	
LANS	4073 - 912	
LANS B	4127 - 966	
LANS C	4174 - 1013	
LANS D	4225 - 1064	
BKC	4352 - 1191	
RTD	4378 - 1217	

8 5/8 " 336 / 250SX, 4 1/2 " 4377 / 150SX  
 DST (1) 3927-3966 (TOP) / 30-60-60-70, REC 180' M, 60' MSW,  
 SIP 1206-1157#, FP 141-151 / 121-151#  
 DST (2) 4098-4152 (LKC B) / TIMES NA, REC 140' OCM (2% OIL),  
 SIP NA, FP 40-101#, HP 2150-2022#  
 DST (3) 4140-4195 (LKC C) / 30-60-60-90, REC 600' GSY OCM  
 (48% OIL), 180' SW, SIP 727-677#, FP 101-181 / 262-363#, HP  
 2150-2130#  
 MICT - CO, PF (LKC C,D&E) 4266-76 & 4224-30, AC 1500G,  
 SWB 4 BFPH (95% OIL), PF (LKC) 4174-82, AC 1500G, SWB 35  
 BF (96% OIL) / 2 HRS, T&R, POP, P 88 BO & 49 BWPD, 6/2/84

INFO RELEASED: 8/22/85 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1985  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS