

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20972-00-00
Spot: S2NW Sec/Twnshp/Rge: 9-16S-13W
3003 feet from S Section Line, 4099 feet from E Section Line
Lease Name: DEUTSCH Well #: 1
County: BARTON Total Vertical Depth: 3388 feet

Operator License No.: 30380
Op Name: HUPFER OPERATING, INC.
Address: PO BOX 216
HAYS, KS 67601

PROD Size: 5.5 feet: 3383
SURF Size: 8.625 feet: 301 w/295 sxs cmt

110"

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/13/2005 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: DENNIS HUPFER Company: HUPFER OPERATING, INC. Phone: (785) 628-8666

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/14/2005 1:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

01-13-2005
Mike's Testing sanded bottom to 3300' and placed 5 sxs cement on top with dump bailer.
Cut casing at 1602'. Tried to pull casing - parted at 50' - placed new collar on and ran back into hole.
Ran back into casing and cut hole at 889'.
Took pump in rate with water pressured to 600# after 2 barrels water.
01-14-2005
RIH with tubing to 1600' - pumped 110 sxs 60/40 pozmix with 300# hulls mixed in to circulate cement to surface.
Pulled tubing and rigged to backside with a swedge.
Pumped 10 sxs 60/40 pozmix with Max. P.S.I. 100#.
Blew packing and slips out of head.
Backside was standing full of cement.
Topped off 5 1/2" casing with 10 sxs 60/40 pozmix.
5 1/2" casing standing full.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3383 | 3388 | | |

RECEIVED
JAN 20 2005
KCC WICHITA

Remarks: SWIFT CEMENTING & ACID SERVICES

Plugged through: TBG

District: 04

Signed Ronald Adams
(TECHNICIAN)

INVOICED

DATE 1-20-05
INV. NO. 2005061086

Form CP-2/3

JAN 14 2005

11/15/76
 0118
 11/15/76

9-15-13*

AL TIPTON #1 DEUTCH C SL NW

BOX 137, HAYS, KS.
 CONTR DUKE DRLLG. CO. CTY BARTON

GEOL HAP PRYOR FIELD TRAPP

E 1920 KB CM2/1/75 CARD ISSUED 3/11/76 IP P 12 BO + 80 BWPD
 ARB 3383-88

API 13-009-20,972

| |
|--|
| |
| |
| |
| |

| SMP | TOPS | DEPTH | DATUM |
|-------|------|-------|-------|
| ANH | 890 | | +1040 |
| HEEB | 3055 | | -1135 |
| TOR | 3075 | | -1155 |
| DOUG | 3077 | | -1167 |
| RR LM | 3136 | | -1216 |
| LKC | 3146 | | -1226 |
| BKC | 3360 | | -1440 |
| ARB | 3382 | | -1462 |
| RTD | 3388 | | -1468 |
| | | | |
| | | | |
| | | | |
| | | | |

8 5/8" 301/295sx, 5 1/2" 3383
 NO LOG
 DST (1) 3370-88/30-30-30-30, 50' GIP,
 120' OIL, 240' W, SIP 938-915#, F#
 58-258#, 352-457#
 MICT - CO TD, SWB 4 BFPH, 30% OIL, 1000'
 OB, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS