

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-23250-00-01
Spot: N2NWSW Sec/Twnshp/Rge: 2-16S-25W
2310 feet from S Section Line, 4620 feet from E Section Line
Lease Name: CLYNE OWWO Well #: 3
County: NESS Total Vertical Depth: 4529 feet

Operator License No.: 5363

MSSC Size: feet: 1933 WITH 525 SX CMT

Op Name: BEREXCO, INC.

PROD Size: 4.5 feet: 4521 WITH 250 SX CMT

Address: PO BOX 20380
WICHITA, KS 67208

SURF Size: 8.625 feet: 304 WITH 225 SX CMT

#147¹⁹

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/29/2004 11:15 AM

Plug Co. License No.: 99996

Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: MARK LEIKER

Company: BEREXCO INC

Phone: (785) 628-6101

Proposed
Plugging
Method:

PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 12/29/2004 3:30 PM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

DV TOOL @ 1933' WITH 525 SX CMT. CMT AT 550' ACCORDING TO WELL RECORDS. TEMPERATURE SURVEY RAN. TUBING SANDED IN @ 3550'. SPOTTED 30 SX CMT & 200# HULLS AT 3533'. CEDAR HILLS BREAK-IN AT 1415'. SPOTTED 40 SX COMMON CMT W/3% CC AT 1350'. WAITED 1 1/2 HOURS. PRESSURED CASING TO 500# & HELD. RAN TUBING TO 850'. TAGGED CMT. PUMPED 55 SX CMT. CMT CIRCULATED. PULLED TUBING & TOPPED OFF WITH 10 SX CMT. CASING STAYED FULL. TIED ONTO BACKSIDE & PUMPED 30 SX CMT. PRESSURED TO 300# & HELD.


Top	Bot	Thru	Comments
4521	4529	OH	
4412	4416		
4397	4402		

RECEIVED
JAN 18 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Michael Maier
(TECHNICIAN)

INVOICED

DATE 1-19-05
INV. NO. 2005061076

Form CP-2/3