

6 031444

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 039-20,356-00-00
SE NE, SEC. 21, T 5 S, R 30 W/E
3300 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5393
Operator: A. L. Abercrombie Inc.
Name & Address: Rt. 1 Box 56
Great Bend, Ks. 67530

Lease Name Robertson Well # 3
County Decatur 134.06
Well Total Depth 4125 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 244

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing License Number 6050
Address Chase, Ks.

Company to plug at: Hour: Day: 17 Month: Oct. Year: 19 90

Plugging proposal received from Bill Sowles
(company name) Abercrombie (phone)

were: 8 5/8 set at 244 w/165 sks cwc. 4 1/2 set at 4120 w/200 sks Perf 4114 - 19 O.H.

4120 - 25. Order sand and common cement. Pull pipe. Order 300 sks 65/35 poz 10% gel
600 lb. hulls. Allied Cement Co. LaRue Water Trucks.

Ran Kelso Wireline to anhy 2200 and placed shot. Hole Open.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 4:30PM Day: 17 Month: Oct. Year: 19 90

ACTUAL PLUGGING REPORT Sand back to 4040 w/4 sks common cement on sand w/bailer.

Recovered 1400 of casing and shot at 1650 - 2200. Sq 8 5/8 w/275 sks cement blend
w/600 lbs. hulls mixed into max psi 500 lbs. Close in psi 300 lbs. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1990
12-21-1990

CONSERVATION DIVISION
Wichita Kansas

Remarks: (additional description is necessary, use BACK of this form.)
did not observe this plugging.

INVOICED
DATE 1-4-91
INV. NO. 30287

Gibbs

Signed Carl Goodrow
(TECHNICIAN)

Carl Goodrow