

6030531

API NUMBER 15-039-20,771-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NWSW, SEC. 18, T. 5 S, R. 30 (W)

2140 feet from S section line
4780 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6467

Lease Name BASTIN Well # 1

Operator: WEST KANSAS OIL - CORP.

County DECATUR 144.50

Name & Address RR 1 Box 77

Well Total Depth 4446 feet

SELDEN, KANSAS

Conductor Pipe: Size _____ feet

67757

Surface Casing: Size 8 5/8 feet 260'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor MURFIN DRLG. Co. License Number 6033

Address WICHITA, KANSAS 67202

Company to plug at: Hour: PM Day: 19 Month: 7 Year: 19 85

Plugging proposal received from STEVE CARLTON

(company name) MURFIN DRLG. Co. (phone) _____

were: 8 5/8 SET @ 260' WITH HOLE FULL OF NO LESS THAN 36 VIS. MUD AND
NO LOSS OR GAIN OF FLUID SPOT CEMENT PLUGS WITH DRILL PIPE ORDER
190 SX. 60/40 PPT 6% GEL 3% CC 8 5/8 W.P. HALLIBURTON CNT. CO.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 7:30 PM Day: 19 Month: 7 Year: 19 85

ACTUAL PLUGGING REPORT SPOT D.P @ 2645' BREAK CIRC. DISPLACE 25% CNT. MIX. LAYDOWN D.P. TO 1750' DISPLACE 100 SX. CNT. MIX. 41 SX. FLOCELL. LAYDOWN D.P. TO 260' DISPLACE 40 SX. CNT. MIX. LAYDOWN D.P. PUSH 8 5/8 W.P. TO KELLY DEPTH FILL HOLE W/10 SX. CNT. MIX. TO BASE OF CELLAR DISPLACE 15 SX. CNT. MIX. IN RATHOLE. PLUG. COMPLETE

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

DATE AUG 07 1985

INV. NO. 97425

7-19 AUG 21 1985

SEP 25 1985

RECEIVED STATE CORPORATION COMMISSION (TECHNICIAN) AUG 5 1985 08-05-1985 CONSERVATION DIVISION