

6 031327

1-23

API NUMBER 15- 023-20,279 -00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE, SEC. 36, T 5 S, R 37 W/EX

4620 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Lease Name McKee Well # 1

Operator: John O. Farmer

County Cheyenne 151.48

Name & Address Box 352

Well Total Depth 4661 feet

Russell, Ks. 67665

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 212

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Emphasis Oil Oper License Number 8241

Address Russell, Ks.

Company to plug at: Hour: AM Day: 23 Month: Jan Year: 19 90

Plugging proposal received from Tom Alm

(company name) Emphasis (phone)

were: 8 5/8" set at 212'. Circ hole with no less than 36 vis mud with no loss or gain of fluid. Balance plugs with mud. Order 200 sks 60/40 poz 6% gel 3% cal cl. Allied Cement Co.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:00AM Day: 23 Month: Jan Year: 19 90

ACTUAL PLUGGING REPORT Spot plugs with drill pipe at 3100' w/25 sks

2130' w/100 sks and Halls.

360' w/75 sks

40' w/10 sks wiper plug.

15 sks rathole

10 sks mousehole

Remarks: Anhy 3071 - 3112 elev. 3381.

(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

INVOICED

DATE 2-15-90

INV. NO. 27456

Signed Carl Goodrow (TECHNICIAN) Carl Goodrow