

6 040874

1-28-88
API NUMBER 15- 023-20,185A-0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

_____, SEC. 36, T 5 S, R 37 (W/E)
660 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9152

Lease Name McKee Well # 34 - 36

Operator: Marexco

County Cheyenne 151.45

Name & Address P.O. Box 706

Well Total Depth 4660 feet

Edmond, Ok. 73034

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet N.A.

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co. License Number _____

Address Ness City, Ks.

Company to plug at: Hour: 4:00 PM Day: 28 Month: Jan Year: 19 88

Plugging proposal received from Marexco

(company name) Marexco Co. (phone) _____

were: 4 1/2" casing set at 4660'; Perf 4342' - 4484'

C.I.B.P. at 4476'.

Ordered 3 sks 60/40 Poz 6% Gel w/1/4# F.C. per sk cement.

Plugging Proposal Received by Dennis L. Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 4:00 PM Day: 28 Month: Jan Year: 19 88

ACTUAL PLUGGING REPORT

Plug w/1 sks cement on C.I.B.P. plus 25 sks 60/40 Poz w/1 sks Hulls. 4071' - 4471';

mud to 2500'; 60 sks cement from 2500' to 2150'; mud to 400'; 40 sks cement from 400' - 200'; mud to 40'; 10 sks cement from 40' to surface;

Minimum depth for Dakota protection 2380' w/top at 2340'.

RECEIVED
STATE CORPORATION COMMISSION
5-12-88
MAY 12 1988

Remarks: Plug O.K.'d by Mr. Don Butcher for Dakota protection.

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 5-17-88

INV. NO. 20641

Signed Dennis L. Hamel (TECHNICIAN)

Dennis L. Hamel

FORM CP-2/3
Rev. 01-84