

6 031006

11-21-87

-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 023-20,104

C SE NE, SEC. 36, T 5 S, R 37 W/E

3300 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6978

Lease Name McKee Well # 1

Operator: Nielson Ent. Inc.

County Cheyenne 161.53

Name & Address Box 370

Well Total Depth 4970 feet

1825 Big Horn Ave

Conductor Pipe: Size feet

Cody Wyoming 82414

Surface Casing: Size 8 5/8 feet 404

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address Oberlin, Kansas

Company to plug at: Hour: AM, Day: 21 Month: Nov Year: 19 87

Plugging proposal received from Gib Sperling

(company name) Nielson Ent. (phone)

were: 8 5/8" set at 404' w/300 sks cwc 4 1/2 set at 4969' w/260 sks.

Prod perms 4670' -4686'. 2 shots/FT at 2200' for black squeeze at 50' below "Dakota"

Anhy at 3112'. Order 300 sks Econolite 65/35 Poz 10% Gel 2% Dicol Cement Blend,

500# Halls, Halliburton Cement Co.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:15AM Day: 21 Month: Nov Year: 19 87

ACTUAL PLUGGING REPORT Squeezed 4 1/2 w/200sks Cement Blend. Max Psi 400#. Close

in Psi 200#. Squeeze 8 5/8" - 4 1/2 Annulus w/100sks. Max PSI 300#. Close in Psi 150#.

Plug complete.

12-29-87

DEC 29 1987

Wichita, Kansas

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 1-7-88

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 19408