

4 060027

11-12

STATE CORPORATION COMMISSION

11-20-89

NOV 20 1989

API NUMBER 15- 023-20,278 - 00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SE NE, SEC. 35, CONSERVATION DIVISION, Wichita, Kansas 37 W/E

2970 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30221

Lease Name Fisher Well #1-35

Operator: Marks Energy, Inc.

County Cheyenne 142.66

Name & Address 1580 Lincoln St. Suite 600

Well Total Depth 5005 feet

Denver, Co. 80203

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 315

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXXXXXXX

Other well as hereinafter indicated

Plugging Contractor Golden Eagle Drilling License Number 8682

Address McCook, NE

Company to plug at: Hour: 11:30AM Day: 12 Month: November Year: 19 89

Plugging proposal received from Dave Paschall

(company name) Golden Eagle Drilling (phone) 308-345-3839

were: Space all plugs with heavy drilling mud through drill pipe.

Order 195 sxs. of 60/40 pos 6% gel 1/4# floccel per sx.

Plugging Proposal Received by Herb Deines (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None XXXXXXXX

Operations Completed: Hour: 11:30AM Day: 12 Month: November Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 3140' with 20 sxs. Anhydrite 3109-3146'
2nd plug at 2220' with 100' sxs. Dakota 1918-2218'
3rd plug at 365' with 40 sxs. Surface pipe to 315'
4th plug at 40' with 10 sxs. wiper plug at 40'
rathole with 15 sxs and mouse hole with 10 sxs.

Remarks: Halliburton Cementing (if additional description is necessary, use BACK of this form.)

INVOICED (I did not observe this plugging.)

DATE 12-4-89

Signed Herb Deines (TECHNICIAN)

INV. NO. 26558

Herb Deines

11-12