

4-031834

6-28

TQ:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-023-20,033 - 0000

C SW NW /4 SEC. 35, 05 S, 37 W  
3300 feet from S section line  
4620 feet from E section line

Operator license# 5393 Lease Fisher well # 1

Operator: A.L. Abercrombie, Inc. County Cheyenne

Address: Rt. 1 - Box 56 Well total depth 4950 feet <sup>160.87</sup>  
Great Bend, Kansas 67530 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 380 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Kelso Casing Pulling License# 6050

Address: Chase, Kansas 67524

Company to plug at: Hour: P.M. Day: 28 Month: June Year: 93

Plugging proposal received from: Dave

Company: Kelso Casing Pulling Phone:           

Were: Order 230 sxs. 65/35 pozmix - 10% gel.  
Sand and common cement.  
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 6:45P.M., Day: 28, Month: June, Year: 93

Actual plugging report: 8 5/8" set @ 380' w/300 sx. cwc. 4 1/2" set @  
4705' w/225 sxs. P.B.T.D. 4667'. Perf. 4577' - 4586'. Shots @ 3090' -  
2100' - Sand back to 4500' w/4 sxs. common cement on sand with bailer.  
Pumped 35 sxs. cement slurry from 2100' to 3090' with 1200 P.S.I.  
Shot off @ 1610'. Laid down skid and rack. Pumped slurry from surface  
to 2100' w/70 sxs. Laid down 4 1/2" casing to 300' circulated w/70 sxs.  
cement blend slurry. Laid down 4 1/2" casing topped off with total of  
175 sxs. cement blend w/500# hulls mixed in. Plug complete.

Remarks: Anhy. 3014' - 3052'.  
Condition of casing(in hole): GOOD     BAD     Anhy.plug: YES X NO      
Bottom plug(in place): YES    , CALC    , NO     Dakota plug: YES    , NO      
Plugged through TUBING    , CASING    . Elevation: 3319 GL    

I **INVOICED** [     ] observe the plugging. Carl Goodrow <sup>AUG - 5 1993</sup>

DATE 8-6-93  
INV. NO. 38265

DA (agent) 8-5-93  
Form CP-2/3