

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-01765-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 30-18S-7W
330 feet from S Section Line, 4950 feet from E Section Line
Lease Name: MEYER Well #: 12
County: RICE Total Vertical Depth: 3218 feet

Operator License No.: 8917
Op Name: GUSTUS, DEAN DBA JD PRODUCTION
Address: 701 MAIN
GENESEO, KS 67444

CIBP Size: feet: 3078
PROD Size: 5.5 feet: 3216
SURF Size: 8.625 feet: 310

#10459

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/28/2004 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTY ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-7397

Proposed Plugging Method: See actual report.

RECEIVED
KCC DISTRICT #2
JAN 7 - 2005

WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 12/28/2004 12:45 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

Set CIBP at 3078' and put 2 sacks of cement on top. Attempted to pull casing; parted at 750'. Pulled casing to 720' and pumped 50 sacks of cement with cotton hulls and calcium chloride. Pulled casing to 360' and circulated cement to surface.

60/40 posmix with 4% gel.

Allied Cement #20232

Remarks:

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 1-20-05
INV. NO. 2005061085