

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-00043-00-00  
Spot: SWSWNW Sec/Twnshp/Rge: 12-17S-9W  
2940 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: LORRAINE Well #: 1-1  
County: ELLSWORTH Total Vertical Depth: 3246 feet

Operator License No.: 3273  
Op Name: LOEB, HERMAN L.  
Address: PO BOX 524  
LAWRENCEVILLE, IL 62439

PROD Size: 4.5 feet: 3175  
SURF Size: 8.625 feet: 200

#105<sup>50</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/29/2004 12:00 PM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: ALAN VRATIL Company: KLIMA WELL SERVICE, INC. Phone: (620) 886-3563

Proposed Plugging Method: See actual report.

RECEIVED  
KCC DISTRICT #2  
JAN 7 - 2005  
WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 12/29/2004 1:45 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Set CIBP at 3016' and put 2 sacks on top; perforated at 1175', 850', and 250'. Ran tubing to 1175' and pumped 35 sacks cement; pulled to 850' and pumped 35 sacks of cement; and pulled tubing to 250' and circulated cement to surface.

60/40 posmix with 4% gel

Allied Cement ticket #19413

RECEIVED  
JAN 20 2005  
KCC WICHITA

Perfs:

Top	Bot	Thru	Comments
3066	3071		

Remarks:

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

INVOICED  
DATE 1-20-05  
INV. NO. 2005061087