

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-00425-00-00
Spot: NE Sec/Twnshp/Rge: 23-29S-33W
2540 feet from N Section Line, 2540 feet from E Section Line
Lease Name: WRIGHT Well #: 2
County: HASKELL Total Vertical Depth: 2712 feet

Operator License No.: 32787
Op Name: KANSAS NATURAL GAS OPERATING, I
Address: PO BOX 818 1200 MAIN STREET
HAYS, KS 67601

PROD Size: 7 feet: 2698 WITH 800 SX CMT
SURF Size: 10.75 feet: 520 WITH 400 SX CMT

88 14

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/10/2005 11:30 AM
Plug Co. License No.: 99997 Plug Co. Name: HALLIBURTON ENERGY SERVICES
Proposal Rcvd. from: STEVE LEHNING Company: KANSAS NATURAL GAS Phone: (620) 675-8185

Proposed
Plugging
Method:

PUMP 400# HULLS WITH 30 SX CMT. MUD SPACER TO 700'. FILL 7" TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND
Date/Time Plugging Completed: 01/10/2005 4:30 PM

WitnessType: COMPLETE (100%)
KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 300# HULLS & 30 SX CMT FOR BOTTOM PLUG. PUMP 65 BBL MUD SPACER TO 800'. PUMP 140 SX CMT FROM 800' TO SURFACE. PRESSURED TO 180 PSIG & SHUT IN. RIG UP TO BACKSIDE. PRESSURED IMMEDIATELY. BACKSIDE FULL. PLUG FELL INSIDE 7". TOPPED OFF WITH 75 SX CMT.

Perfs:


Top	Bot	Thru	Comments
2695			
2648	2676		
2624	2634		

RECEIVED
JAN 21 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY HALLIBURTON. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Jim Holland PART # _____
(TECHNICIAN)

INVOICED

DATE: 1-21-05
INV. NO. 2005061092

Form 0023