

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20583-00-00
Spot: E2NESW Sec/Twnshp/Rge: 35-19S-1W
~~2118~~ feet from S Section Line, 3098 feet from E Section Line
Lease Name: ELWOOD / KOEHN E M Well #: 2
County: MCPHERSON Total Vertical Depth: 2940 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

PROD Size: 4.5 feet: 2940 150 SX CMT
SURF Size: 8.625 feet: 175 150 SX CMT

\$95⁵⁵

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/19/2004 9:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: ALAN L DEGOOD Company: AMERICAN ENERGIES CORPORAT Phone: (316) 263-5785

Proposed Plugging Method: Sand to 2,845' & top with 4 sxs. cement. Shoot casing off & pull same. Run tubing to 425' & spot 35 sxs. cement. Pull tubing to 250' & circulate & circulate cement to the surface.

RECEIVED
KCC DISTRICT #2
JAN 13 2005

WICHITA, KS

Plugging Proposal Received By: MICHAEL WILSON Witness Type: PARTIAL
Date/Time Plugging Completed: 11/24/2004 1:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 2,850' & topped with 4 sxs. cement. Shot casing off @ 1,750' & pulled same. Ran tubing to 442' & spotted 2 yards slurry mix (50 sxs. cement). Pulled tubing to 250' & circulated 7 yards slurry mix (175 sxs. cement) to the surface.

Perfs:

Top	Bot	Thru	Comments
2893	2923		

Remarks: USED SLURRY MIX BY HESSTON CONCRETE INC. INVOICE #76948.

Plugged through: TBG

District: 02

Signed Michael Wilson
(TECHNICIAN)

INVOICED
DATE 1-20-05
INV. NO. 2005061084