

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20759-00-01
Spot: SWNENW Sec/Twnshp/Rge: 33-17S-2W
4290 feet from S Section Line, 3960 feet from E Section Line
Lease Name: GABRIELSON SWD Well #: 2
County: MCPHERSON Total Vertical Depth: 2520 feet

Operator License No.: 33005
Op Name: RANDON PRODUCTION COMPANY LL
Address: 2761 REMINGTON RD
MARION, KS 66861

PROD Size: 2.875 feet: 2563
PROD Size: 4.5 feet: 3646
SURF Size: 8.625 feet: 266

8190

Well Type: SWD UIC Docket No: D24632.0 Date/Time to Plug: 11/08/2004 12:00 PM
Plug Co. License No.: 33005 Plug Co. Name: RANDON PRODUCTION COMPANY LLC
Proposal Rcvd. from: RANDY SVITAK Company: RANDON PRODUCTION COMPAN Phone: (620) 924-5437

Proposed Plugging Method: 2 7/8" tubing cemented in place to 700'. There is junk in hole at 1,300' inside tubing - will not circulate. Shoot casing off & pull same. Run tubing & spot 35 sxs. cement @ 700'. Pull tubing to 315' & circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/09/2004 5:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Pulled 545' of tubing. Shot casing off at 547' & pulled same. Ran tubing to 545' & circulated 276 sxs. cmt. to the surface.

Perfs:

Top	Bot	Thru	Comments
2476	2510		

RECEIVED
KCC DISTRICT #2
JAN 13 2005
WICHITA, KS

Remarks: USED 60/40 POSMIX W/4% GEL BY RANDON PRODUCTION CO., LLC. INVOICE #2.

Plugged through: TBG

District: 02

Signed Michael Wilson
(TECHNICIAN)

INVOICED
DATE 1-20-05
INV. NO. 2005061089