

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER ¹⁵ 039-20,342 - 00-00 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR A. L. Abercrombie, Inc. OPERATORS LICENSE NO. 5393

ADDRESS Rt. #1, Box 56, Great Bend, Ks. 67530 PHONE # (316) 793-8186

LEASE (FARM) Robertson WELL NO. 2 WELL LOCATION NE SE COUNTY Decatur

SEC. 21 TWP. 5 RGE. 30 (E) or (W) TOTAL DEPTH 4112 PLUG BACK TO 2563

Check One:

OIL WELL _____ GAS WELL _____ D & A _____ SWD or INJ WELL X DOCKET NO. D-18,434

SURFACE CASING SIZE 10 3/4 SET AT 211' CEMENTED WITH 150 SACKS

CASING SIZE 7" SET AT 2600' CEMENTED WITH 650 SACKS

PERFORATED AT 2356-2404

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL In compliance with rules and regulations State of Kansas

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Soon as Possible

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

E. L. Abercrombie PHONE # (316) 793-8186

ADDRESS Rt. #1, Box 56, Great Bend, Ks. 67530

PLUGGING CONTRACTOR A. L. Abercrombie, Inc. LICENSE NO. 5393

ADDRESS Rt. #1, Box 56, Great Bend, Ks. 67530 PHONE # (316) 793-8186

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT RECEIVED STATE CORPORATION COMMISSION SIGNED: E. L. Abercrombie
(Operator or Agent)

DATE: 6-1-90

JUN 4 1990
0604-90
CONSERVATION DIVISION
Wichita, Kansas

4

4/00

6/90

KANSAS DRILLERS LOG

API No. 15 — 039 — 20,342 - 60-60
 County Number

S. 21 T. 5S R. 30 W
 Loc. 150' NW of C NE SE
 County Decatur

Operator
 A. L. Abercrombie, Inc.

Address
 801 Union Center, Wichita, Kansas 67202


Well No. 2 Lease Name ROBERTSON

Footage Location
 554 feet from (N) (S) line 776 feet from (E) (W) line

Principal Contractor
 Abercrombie Drilling, Inc. Geologist
 Charles Johnson

Spud Date
 June 18, 1976 Total Depth
 4112' P.B.T.D.
 2460

Date Completed
 June 24, 1976 Oil Purchaser
 SWDW



Elev.: Gr. _____
 DF _____ KB _____

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	13-1/2"	10-3/4"		211 K.B.	Sun Quickset	150	None
Disposal	9-7/8"	7"		2600'	50/50 Posmix Common	550 100	6% Gel 2% gel & 10% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			2		2356-2404

Size	Setting depth	Packer set at
2" V I P	2304	2300

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
None	

RECEIVED
 JUN 4 1990
 CONSERVATION DIVISION
 Wichita, Kansas

INITIAL PRODUCTION

Date of first production
 SWDW

Injection rate satisfactory

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold)
 Disposing Interval
 2356-2404

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator A. L. Abercrombie, Inc. DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. 2 Lease Name ROBERTSON

S 21 T 5S R 30 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Clay & Sand	0	103		
Sand	103	187		
Shale	187	2190		
Shale-Gyp.	2190	2589		
Anhydrite	2589	2627		
Shale	2627	3586		
Lime & Shale	3586	3668		
Shale & Lime	3668	3918		
Lime & Shale	3918	3943		
Lime	3943	4112		
Rotary Total Depth		4112		
<p>DST #1 (3883'-3918') 30", 45", 60", 45". Weak blow - Rec. 50' thin mud, IFP 25-30# IBHP 1247#, FFP 43-49#, FBHP 1160#.</p> <p>DST #2 (3988'-4010') 30", 45", 30", 45". Weak blow for 30 min., recovered 40' thin oil spotted mud. IFP 42-42#, IBHP 136#, FFP 42-42# No FBHP.</p> <p>DST #3 (4087'-4112') 30", 45", 30" 45". Weak blow for 30 minutes, recovered 5' of mud. IFP 30-30#, IBHP 68#, FFP 30-35# FBHP 48#.</p>				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Signature: *Jerry A. Langrehr*

Jerry A. Langrehr, Executive Vice President

Title

July 12, 1976

Date



15-039-20342-08-00

Kansas Corporation Commission

MIKE HAYDEN	GOVERNOR
KEITH R. HENLEY	CHAIRMAN
RICH KOWALEWSKI	COMMISSIONER
JACK SHRIVER	COMMISSIONER
JUDITH MCCONNELL	EXECUTIVE DIRECTOR
FRANK A. CARO, JR.	GENERAL COUNSEL

CONSERVATION DIVISION
 SHARI FEIST ALBRECHT, DIRECTOR
 200 Colorado Derby Bldg.
 202 W. 1st Street
 Wichita, KS 67202-1286
 (316) 263-3238

**NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION**

July 23, 1990

A.L. Abercrombie, Inc.
 Rt. #1, Box 56
 Great Bend, KS 67530

Robertson #2
 NE SE 21-05-30W
 Decatur County, KS
 API No. 15-039-20,342

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams

David P. Williams
 Production Supervisor

District: #4, 2301 E. 13th
 Hays, KS 67601
 (913) 628 - 1200