

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 077 00720703 - 00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 7/16/81.

Well Operator: Woolsey Operating Company LLC KCC License #: 33168  
(Owner / Company Name) (Operator's)

Address: 125 North Market City: Wichita

State: Kansas Zip Code: 67202 Contact Phone: ( 620 ) 886 - 5606 ext 27

Lease: Robinson Well #: G-1 Sec. 21 Twp. 32 S. R. 8  East  West

- S/2 - NW - SE Spot Location / QQQQ County: Harper

1650 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

1980 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8" 24# Set at: 267' Cemented with: 250 Sacks

Production Casing Size: 4 1/2" 10.5# Set at: 3899' Cemented with: 200 Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs from 3680' to 3684', 3666' to 3676', CIBP @ 3663' & perfs from 3634' to 3644.

Elevation: 1426' ( G.L. /  K.B.) T.D.: 3900' PBTD: 3663' Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Sand from 3663' to 3584' place 4 sax cement on top w/ bailer. 35 sax @ 1325', 35 sax @ 800', circulate to surface @ 325'. Use 60/40 poz w/ 4% gel.

**RECEIVED  
JAN 25 2005  
KCC WICHITA**

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

**Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.**

List Name of Company Representative authorized to be in charge of plugging operations: Carl W. Durr

Phone: ( 620 ) 886 - 5606 ext 27

Address: SAA City / State: \_\_\_\_\_

Plugging Contractor: Clarke Corporation KCC License #: 5105  
(Company Name) (Contractor's)

Address: Medicine Lodge, Kansas Phone: ( 620 ) 886 - 5665

Proposed Date and Hour of Plugging (if known?): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 1/24/05 Authorized Operator / Agent: Carl W. Durr  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor   Brian J. Moline, Chair   Robert E. Krehbiel, Commissioner   Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

Woolsey Operating Company, LLC  
125 N. Market, Suite 1000  
Wichita, KS 67202-1775

January 26, 2005

Re: ROBINSON #G-1  
API 15-077-20703-00-00  
S2NWSE 21-32S-8W, 1650 FSL 1980 FEL  
HARPER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #2  
3450 N. Rock Road, Suite 601  
Wichita, KS 67226  
(316) 630-4000

Sincerely



David P. Williams  
Production Supervisor