

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
**This Form must be Typed
Form must be Signed
All blanks must be Filled**

API # 15-135-20128-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 3/2/68.

6/05

Well Operator: VESS OIL CORPORATION KCC License #: 5030

Address: 8100 E. 22nd Street North, Bldg. 300 City: Wichita

State: KS Zip Code: 67226 Contact Phone: (316) 682-1537 X103

Lease: Lehner Well #: 12 Sec. 24 Twp. 20S S. R. 24W East West

- C - NW - SE Spot Location / QQQQ County: Ness

1980' Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1980' Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8 Set at: 330' Cemented with: 170 Sacks

Production Casing Size: 4-1/2" Set at: 4377' Cemented with: 150 Sacks

List (ALL) Perforations and Bridgeplug Sets: Miss - 4374-77'; OH - 4377-4429' DV-1526' w/425 sx - circ.

Elevation: 2312' (G.L. / K.B.) T.D.: 4429' P.B.T.D.: 4429' Anhydrite Depth: 1533'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): In accordance with KCC rules and regulations

**RECEIVED
KANSAS CORPORATION COMMISSION
JAN 24 2005
CONSERVATION DIVISION
WICHITA, KS**

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? NA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Ken Rupp

Phone: (785) 798-5260

Address: 112 N. High City / State: Ness City, KS 67560

Plugging Contractor: Swift Services, Inc. KCC License #: 32382

Address: P.O. Box 466, Ness City, KS 67560 Phone: (785) 798-2300

Proposed Date and Hour of Plugging (if known?): ASAP

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 1/21/05 Authorized Operator / Agent: [Signature]

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

10/05

Great Bend, Kansas

DRILLERS LOG

From #12 Lehner

CASING RECORD: Steel, COMPANY: R. V. Lehner, DESCRIPTION: C/NW SE Section 24-208-24W, Ness County, Kansas
Ran 330' of new 8-5/8" surface casing. CONTRACTOR: Strata Drilling, Inc.

TOTAL DEPTH: 4387' COMMENCED: March 11, 1968 ELEVATION: 2312' KB
COMPLETED: March 20, 1968

15-135-20128-00-00

FORMATION	DEPTH	FROM	TO	REMARKS
Surface Clay & Post Rock		0	100	Ran 330' of new 8-5/8" surface casing; set and cemented with 170 sacks of cement and 2% gel. Plug down at 11:40 P. M. March 11, 1968.
Clay, Shale, Sand & Red Bed		100	344	
Shale & Shells		344	1000	
Shells, Shale & Sand		1000	1200	
Shale & Red Bed		1200	1533	
Anhydrite		1533	1550	
Red Bed & Shale		1550	1629	
Shale & Lime		1629	2575	
Lime		2575	2808	
Lime & Shale		2808	3995	
Lime		3995	4282	
Lime & Chert		4282	4387	

Total Depth 4387'


RECEIVED
KANSAS CORPORATION COMMISSION
JAN 24 2005
CONSERVATION DIVISION
WICHITA, KS

By: _____
I certify that this is a true and correct copy of the above log to the best of my knowledge.
Ran 139 joints of new 4 1/2" set and cemented at 4377' with 150 sacks of posmix, salt saturated and 2% gel 1st stage. Stage collar set at 1526'. Ran 425 sacks of Halliburton lite cement 2nd stage. Plug down at 6:00 A. M. March 20, 1968.

700 4-2-4 3-3-4 4 4
800 3-2-3 3-3-7-2-1
810 4-4-4 2-3/5-4-5-4-5
820 4-5-4 4-3/4-6-5-4-5
830 2-2-3 2-2-2-2-2-2-2
840 2-2-2 2-2-2-2-2-2-2
850 2-2-2 2-2-2-2-2-2-2
860 2-2-2 2-2-2-2-2-2-2
870 2-2-2 2-2-2-2-2-2-2
880 4-4-4 2-3-3-4-0-5
890 5-4-4 5-4-4-5-4-5
900 4-4-4 4-4-4-4-4-4-4
910 3-3-3 3-3-3-3-3-3-3
920 3-3-3 3-4-2-1-2-1-1
930 3-4-3 3-2-2-2-2-2-2
940 4-4-4 4-3-3-4-3-4-4
950 1-3-2-3 1-3-2-3-4-4-4
960 5-4-4 5-4-4-5-4-5-4-5
970 4-4-4 4-4-4-4-4-4-4
980 4-4-4 4-4-4-4-4-4-4
990 4-4-4 4-4-4-4-4-4-4

STATE OF KANSAS)
COUNTY OF BARTON)
I certify that this is a true and correct copy of the above log to the best of my knowledge.
STRATA DRILLING, INC.
Charles W. Steincamp, President

Subscribed and sworn to before me this 20th day of March, 1968.



Elaine H. Taylor, Notary Public



CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Vess Oil Corporation
8100 E. 22nd N. Bldg. 300
Wichita, KS 67226

January 26, 2005

Re: LEHNER #12
API 15-135-20128-00-00
NWSE 24-20S-24W, 1980 FSL 1980 FEL
NESS COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely

David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888