

RECEIVED

SEP 19 2003

KCC WICHITA

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-051-22,617-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Younger Inc KCC LICENSE # 32580 <sup>1/04</sup>  
(owner/company name) (operator's)

ADDRESS P.O. Box 451 CITY HAYS

STATE Ks. ZIP CODE 67601 CONTACT PHONE # (785) 625-3107

LEASE B. Younger WELL# 1 SEC. 7 T. 14 R. 17 (East West)

SE-NE-NE-7/4 SPOT LOCATION/QQQQ COUNTY ELLIS

4290 FEET (in exact footage) FROM SN (circle one) LINE OF SECTION (NOT Lease Line)

330 FEET (in exact footage) FROM EW (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#           

CONDUCTOR CASING SIZE            SET AT            CEMENTED WITH            SACKS

SURFACE CASING SIZE 8-5/8 SET AT 206' CEMENTED WITH 125 SACKS

PRODUCTION CASING SIZE 4-1/2 SET AT 3600' CEMENTED WITH 125 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4 shots per ft / .43" size / 3538' - 3550'

ELEVATION 1994/1999' T.D. 3600' PBTD            ANHYDRITE DEPTH 1202'  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING AS per KCC Rep Pat Steab Specification

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED?  IS ACO-1 FILED? yes

If not explain why?           

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Younger Inc. PHONE# (785) 625-3107

ADDRESS P.O. Box 451 City/State Hays, Ks. 67601

PLUGGING CONTRACTOR Francis Tarrant Swift Services, Inc. KCC LICENSE # 31821 <sup>333822/04</sup>  
(company name) (contractor's)

ADDRESS 119 Toward Ave. 67560 PHONE # (785) 623-9438 cell

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 9-24-03 Plugged

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 9/16/03 AUTHORIZED OPERATOR/AGENT: [Signature]  
(signature)


AFFIDAVIT OF COMPLETION FORM

ACO-1

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed. Circle one: (Oil) gas, dry, SWD, OWVO, injection. Type and complete API sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316)263-3238.

OPERATOR Drolling Ltd. of Colorado API NO. 15-051-22,617  
 ADDRESS 410 - 17th St., Suite 1140 COUNTY Ellis  
Denver, Colorado 80202 FIELD WYOUNGER SW  
 \*\*CONTACT PERSON Floyd H. Hoffman PROD. FORMATION Arbuckle  
 PHONE (302) 623-6144 LEASE B. Younger  
 PURCHASER Clear Creek WELLS NO. 1  
 ADDRESS P.O. Box 1045 WELL LOCATION SE 1/4 NE 1/4  
McPherson, Kansas 67460 Ft. from \_\_\_\_\_ Line and \_\_\_\_\_  
 DRILLING CONTRACTOR C and B Drilling Co. Ft. from \_\_\_\_\_ Line of \_\_\_\_\_  
 ADDRESS 410 - 17th St., Suite 1140 the SEC. 7 TWP. 14S RGE. 17W  
Denver, Colorado 80202

PLUGGING Halliburton  
 CONTRACTOR  
 ADDRESS Hays, Kansas



WELL PLAT  
 KCC  
 KGS  
 MISC  
 (Office Use)

TOTAL DEPTH 3600 PSTD  
 SPUD DATE 10-17-81 DATE COMPLETED 12-6-81  
 ELEV: GR 1994 DF \_\_\_\_\_ KB 1999

DRILLED WITH (CABLE) (NOTARY) (ATR) TOOLS (New) / (Used) casing.  
 CASING RECORD

Report of all strings set-- surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement?	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24#	206'	Reg. Portland	125	2% Gal & 3% Cl
Production	7-7/8"	4-1/2"	9 1/2#	3600'	Reg. Portland	125	Salt gran. blended Cal. Seal blended
1240'-Surf. (EO Tool)- cemented from Anhydrite to surface						300	

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	.43"	3538'-3550'

TUBING RECORD		
Size	Setting depth	Packers set at
2-3/8"	3565'	None

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth interval treated
Acidized W/4000 Gal. 20% MOD-202	3538'-3550'

Date of first production December 6, 1981 Producing method (flowing, pumping, jet lift, etc.) Pumping Gravity \_\_\_\_\_  
 RATE OF PRODUCTION PER 24 HOURS 10 bbls. Gas Trace Water 75% Gas-oil ratio \_\_\_\_\_ CFPB \_\_\_\_\_  
 Disposition of gas (vented, used on lease or sold) Vented Perforations 3538'-3550'

\*\*The person who can be reached by phone regarding any questions concerning this information. A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.

CEMENTED WITH \_\_\_\_\_ SACKS  
SURFACE CASING SIZE 8-5/8 SET AT 206' CEMENTED WITH 125 SACKS  
PRODUCTION CASING SIZE 4-1/2 SET AT 3600' CEMENTED WITH 125 SACKS  
LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4 shots per ft / .43" size / 3538' - 3550'  
ELEVATION 1994 / 1999' T.D. 3600' P.B.T.D. \_\_\_\_\_ ANHYDRITE DEPTH 1202'  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING As per KCC Reg Pat Steab Specification

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? \_\_\_\_\_ IS ACO-1 FILED? yes

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: \_\_\_\_\_

Younger Inc. PHONE# (785) 625-3107

ADDRESS P.O. Box 451 City/State Hays, Ks. 67601

PLUGGING CONTRACTOR Frank Tappert KCC LICENSE # 31821  
(company name) (contractor's)

ADDRESS 1119 Toulon Ave. PHONE # (785) 623-9438 Cell.

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) \_\_\_\_\_

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 9/16/03 AUTHORIZED OPERATOR/AGENT: Jeff [Signature]  
(signature)

Name of lowest fresh water producing stratum \_\_\_\_\_ Depth 48'  
 Estimated height of cement behind Surface Pipe Circ. to Surf.  
 DV USED? FO Tool used

WELL LOG

Formation Description, Contents, etc.	Top	Bottom	Name	Depth
ANHYDRITE	1202'	1243'	ANHYDRITE	1202
TOPEKA- Shale and limestone	2980'	3251'	TOPEAK	2980
HEERINCER- Shale and limestone	3251'	3268'	HEEBNER	3250
TORONTO- Shale and limestone	3268'	3295'	TORONTO	3268
LANSING- Limestone and shale	3295'	3509'	LANSING	3295
BASE L-KC- Shale and limestone and sandstone	3509'	3531'	BASE L-KC	3509
ARBUCKLE- Dolomite	3531'	3600'	ARBUCKLE	3531
DST 3525'-3540' 15-30-30-30				
Rec. 7' MCO				
FP 8-24#, 18-31#				
SIP 817-641#				
DST 3534'-3546'				
15-30-30-60				
Rec. 31' MCO				
FP 15-25#, 29-35#				
SIP 1085-1092, 1060-1065#				

A F F I D A V I T

STATE OF COLORADO, COUNTY OF DENVER SS, \_\_\_\_\_

Floyd H. Hoffman \_\_\_\_\_ OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS Exploration Manager (FOR)(OF) Dreiling Ltd. of Colorado

OPERATOR OF THE B. Younger LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 1 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 6th DAY OF December, 19 81, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) Floyd H. Hoffman

SUBSCRIBED AND SWORN BEFORE ME THIS 11th DAY OF December, 19 81

Lorraine C. Murphy  
 NOTARY PUBLIC

MY COMMISSION EXPIRES: Sept. 2, 1983