

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
245 North Water  
WICHITA, KANSAS 67202

Rev. 6-3-74  
FORM CP-1

WELL PLUGGING APPLICATION FORM  
File One Copy

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 14 1979  
8-14-79  
CONSERVATION DIVISION  
Wichita, Kansas

API Number 15 - 163 - 20825-0000 (of this well)  
Lease Owner Brandt Oil Company  
Address 1103 Douglas Bldg. Wichita, Kansas, 67202  
Lease (Farm Name) Hanson Estate Well No. 1  
Well Location 50'S SE SW SE Sec. 2 Twp. 6 S Rge. (E) (W) 20 W  
County Rooks Total Depth 3583' Field Name \_\_\_\_\_  
Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ Rotary D & A \_\_\_\_\_  
Well Log attached with this application as required yes  
Date and hour plugging is desired to begin immediately

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Brandt Oil Company Address 1103 Douglas Bldg. Wichita

Plugging Contractor Kelso Casing Pulling License No. 683

Address Box 176 Chase, Kansas, 67524

Invoice covering assessment for plugging this well should be sent to:

Name Brandt Oil Company

Address 1103 Douglas Bldg. Wichita, Kansas, 67202

and payment will be guaranteed by applicant or acting agent.

Signed: R. Daniel Kelso  
Applicant or Acting Agent

Date: 8 - 11 - 79


KANSAS

WELL COMPLETION REPORT AND DRILLER'S LOG

API No. 15 — 163 — 20825-0000  
 County Number

S. 2 T. 6S R. 20 <sup>E</sup> <sub>W</sub>  
 Loc. 50' S SE SW SE

Operator Brandt Oil Company  
 Address 1103 Douglas Building Wichita, Kansas  
 Well No. # 1 Lease Name Hanson Estate  
 Footage Location 280 feet from (N) (S) line 1650 feet from (E) (W) line  
 Principal Contractor LawBanco Drlg. Co Geologist Earl O Brandt  
 Spud Date 7-5-1978 Date Completed 7-13-1978 Total Depth 3585 P.B.T.D. 3583  
 Directional Deviation \_\_\_\_\_ Oil and/or Gas Purchaser \_\_\_\_\_

County Rooks  
 640 Acres  
 N  
  
 Locate well correctly  
 Elev.: Gr. 2069  
 DF 2072 KB 2074

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{4}$	8 5/8	22	241	Common	160	3% Cacl
Production	7 7/8	4 $\frac{1}{2}$	9.5	3582		75	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

RECEIVED  
 STATE CORPORATION  
 8-14-79  
 AUG 14 1979

INITIAL PRODUCTION

CONSERVATION DIVISION  
 WICHITA

Date of first production \_\_\_\_\_ Producing method (flowing, pumping, gas lift, etc.) \_\_\_\_\_  
 RATE OF PRODUCTION PER 24 HOURS  
 Oil \_\_\_\_\_ Gas \_\_\_\_\_ Water \_\_\_\_\_ Gas-oil ratio \_\_\_\_\_  
 bbls. MCF bbls. CFPB  
 Disposition of gas (vented, used on lease or sold) \_\_\_\_\_ Producing interval(s) \_\_\_\_\_

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Brandt Oil Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. #1	Lease Name Hanson Est.	Dry Hole
S <u>2</u> T <u>6s</u> R <u>20</u> <sup>E</sup> <sub>W</sub>		

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
sand & gravel	0	295		
shale	295	560		
Wtr. sd	560	625		
sd & sh	625	910		
lm & sh	910	985		
Sd shale	985	1110		
Lm & Gyp.	1110	1380		
Sh	1380	1658		
Anh	1658	1685		
Lm & Sh	1685	2540		
Sh	2540	2570		
Lm	2570	2850		
Lm & Sh	2850	2895		
Lm	2895	2975		
Sh & Lm	2975	3073		
Lm Chalky	3073	3260		
Sh Blk (Heebner)	3260	3264		
Lm den.	3264	3268		
Sh	3268	3286		
Lm Bn. hard	3286	3296		
Lm/sh stk (Lan.)	3296	3492		
Shale gry-red	3492	3536		
Lm	3536	3541		
Shale	3541	3546		
Sand Porous show oil (Reagan)	3546	3562		
Granite Wash	3562	3579		
Weathered granite	3579	3585		
RTD	3585			

RECEIVED  
STATE CORPORATION COMMISSION

AUG 14 1979

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<p align="center"><i>Carl Brandt</i> Signature</p> <p align="center">Geologist Title</p> <p align="center">7-25-1978 Date</p>



15-163-20825-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water

WICHITA, KANSAS 67202

Telephone (316) 263-3238

August 14, 1979

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Hansen Estate
Description	50' S SE SW SE Sec. 2-6S-20W
County	Rooks
Total Depth	3583'
Plugging Contractor	Kelso Casing Pulling


Brandt Oil Company  
1103 Douglas Building  
Wichita, Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,

  
J. Lewis Brock, Administrator

Mr. Marion Schmidt, 2104 Canterbury Rd., Hays, Kansas 67601  
is hereby assigned to supervise the plugging of the above  
named well.