

RECEIVED
STATE CORPORATION COMMISSION

JAN 10 1963
1-10-63
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
500 INSURANCE BUILDING
212 NORTH MARKET
WICHITA 2, KANSAS

WELL PLUGGING APPLICATION FORM
File One Copy

15-039-00540-0000

Lease Owner Continental Oil Company Address Drawer 367, Plainville, Kansas
(Applicant)

Lease (Farm Name) C. E. Feely Well No. 3

Well Location SE, NE, SW Sec. 2 Twp. 5S Rge. 27 (X) (W)

County Decatur Field Name (if any) Feely

Total Depth 3,820' Oil Gas Dry Hole

Was well log filed with application? yes If not, explain: _____

Date and hour plugging is desired to begin January 21, 1963

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of person on the lease in charge of well for owner W. E. Henry

c/o Continental Oil Company Address Jennings, Kansas

Plugging Contractor Forbes Casing Pulling, Inc.

Plugging Contractor's License No. _____

Address Great Bend, Kansas


Invoice covering assessment for plugging this well should be sent to Continental

Oil Company Address Drawer 367, Plainville, Kansas

and payment will be guaranteed by applicant.

This well is to be used as a water supply well for our Feely Field Waterflood. We have Kansas Agriculture Department approval to appropriate fresh water for beneficial use. Our plans are to pull the 5 1/2" casing, plug the hole to the bottom of the surface pipe, and produce fresh water through the 9 5/8" casing.

9 5/8", 36 lb., 8 RT, J-55 casing set at 268' w/300 sacks cement circulated.
5 1/2", 14 lb., 8 RT, J-55 casing set at 3,819' w/200 sacks cement.



Applicant or Acting Agent

Date January 9, 1963

KJQ-drs
CRW File

15-039-00540-00-00

C. E. Feely No. 3
1650' FS & 2310' FW
lines of Section 2,
T5S, R27W, Decatur
County, Kansas

W E L L L O G

Continental Oil Company 100%
Drilled by Nye & Snell
Drilling Company
Spudded: 6-4-54
Completed: 6-15-54

0	-	99'	Clay and Sand	
99	-	258'	Sand	
258	-	278'	Clay (Blue)	- 9 5/8" casing set at 268'
278	-	1107'	Shale	cemented with 300 sacks. Cement
1107	-	1270'	Sand & Pyrite	circulated.
1270	-	1470'	Shale & Sand	
1470	-	1770'	Blue shale & Sand	
1770	-	1830'	Shale, Iron, & Gyp	
1830	-	2210'	Red Bed & Shale	
2210	-	2244'	Anhydrite	
2244	-	2510'	Shale & Shells	
2510	-	2640'	Shale	
2640	-	2778'	Shale, Lime, & Iron Streaks	
2778	-	3069'	Shale & Lime	
3069	-	3275'	Shale & Lime	
3275	-	3320'	Lime & Shale	
3320	-	3510'	Shale & Lime	
3510	-	3580'	Lime & Shale	
3580	-	3584'	Heebner Shale	
3584	-	3635'	Shale & Lime	
3635	-	3672'	Limed Shale	
3672	-	3707'	Shale & Lime	
3707	-	3765'	Cherty Lime	
3765	-	3800'	Lime	
3800	-	3815'	Shale & Lime	
3815	-	3820'	Lime & Shale	T.D. - 5 1/2" casing set at 3819'
				cemented with 200 sacks.
				Top of cement 2670'.

MAR 15 1963
3-15-63
CONSERVATION DISTRICT
Wichita, Kansas



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

January 10, 1963

WELL PLUGGING AUTHORITY

Well No. 3
Lease Feely
Description SE NE SW 2-5-27W
County Decatur

Continental Oil Co.
Drawer 367
Plainville, Kansas

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Very truly yours,

J. P. ROBERTS
Assistant Petroleum Conservation
Director

Mr. W. L. Nichols Moreland, Kansas
is hereby assigned to supervise the plugging of the above
named well.

