

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

Rev. 6-3-74
FORM CP-1

RECEIVED
STATE CORPORATION COMMISSION

JAN 12 1976
01-12-1976
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15 - 029 - 20323-00-00 (of this well)
Lease Owner Cities Service Oil Company
Address P. O. Box 300 Tulsa, Oklahoma 74102
Lease (Farm Name) SCHMAHL Well No. #1
Well Location SW SE SW Sec. 22 Twp. 5S Rge. (E) 30 (W)
County Decatur Total Depth 3654' Field Name _____
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 4:30 p.m. December 24, 1975

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Don Favinger Address Hill City, Kansas 67642

Plugging Contractor Abercrombie Drilling, Inc. License No. #746

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name Cities Service Oil Company

Address P. O. Box 300 Tulsa, Oklahoma 74102

and payment will be guaranteed by applicant or acting agent.

Signed: Jerry A. Langrehr
Applicant or Acting Agent

Jerry A. Langrehr
Date: January 9, 1976

CONTRACTOR'S WELL LOG

15-139-20323-00-00

OPERATOR: Cities Service Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: SCHMAHL #1
 LOCATION: SW SE SW Sec. 22-5S-30W
 Decatur County, Kansas
 SPUD DATE: December 13, 1975
 COMPLETION DATE: December 24, 1975

0	95	Clay
95	145	Sand
145	450	Shale
450	2420	Shale & Sand
2420	2591	Shale & Shells
2591	2623	Anhydrite
2623	2640	Shale & Shells
2640	2759	Shale
2759	2984	Shale & Sand
2984	3337	Shale & Lime
3337	3585	Lime & Shale
3585	3654	Lime
3654	3954	Lime & Shale
3954	4178	Lime
4178	4279	Shale & Lime
4279	4390	Lime & Shale
4390	4445	Lime
4445	4493	Shale & Lime & Chert
4493	4575	Lime
	4575	Rotary Total Depth

Spudded in @ 10:15 a.m. December 12, 1975. Drilled 228' of 12 1/4" hole. Ran 6 jts. of 8 5/8" surface 217' Set @ 225'. Cemented with 150 sx. of Posmix Type "A". Cement with 2% ca. cl. Plug was down @ 3:45 p.m. December 12, 1975. Drilled from under surface @ 3:45 a.m. December 13, 1975. Plugged and Abandoned: 1st Plug was Set @ 1600' with 70 sx. cement; 2nd Plug was Set @ 200' with 20 sx. cement; 3rd Plug was Set @ 40' with 10 sx. cement. State Plugger: Gilbert Balthazor Plug was down @ 4:30 p.m. December 24, 1975.

RECEIVED
 STATE CORPORATION COMMISSION

Anhydrite 2584'
 B/Anhydrite 2623'

JAN 12 1976
 1-12-76
 CONSERVATION DIVISION
 Wichita, Kansas


STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Jerry A. Langrehr-Executive Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the SCHMAHL #1 SW SE SW Section 22-5S-30W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

By: Jerry A. Langrehr
 Jerry A. Langrehr-Exec. V.P.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 9th day of January, 1976.



Sandra Richman
 Sandra Richman - Notary Public

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

WICHITA, KANSAS

New Address
245 North Water
Wichita, Kansas 67202

December 30, 1975

15-039-20323-00-00

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Schmahl "A"
Description	SW SE SW Sec. 22-5-30W
County	Decatur
Total Depth	4575
Plugging Contractor	Abercrombie Drilling, Inc


Cities Service Oil Company
209 East William
Wichita, KS 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Gilbert Balthazor, P. O. Box 9, Route #1, Palco, KS 67657
is hereby assigned to supervise the plugging of the above
named well.