

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21543-00-0001 *KCC RSP 1-31-05*
Spot: SWSE Sec/Twnshp/Rge: 8-14S-13W
660 feet from S Section Line, 1650 feet from E Section Line
Lease Name: CARTER Well #: 2
County: RUSSELL Total Vertical Depth: 3368 feet

Operator License No.: 4952
Op Name: SCHLOBOHM, STARR F.
Address: 47 MICHAWANIC ROAD #3D
SANBORNVILLE, NH 03872

PROD Size: 4.5 feet: 2550
SURF Size: 8.625 feet: 200

\$10945

Well Type: OEOR UIC Docket No: E2090.1 Date/Time to Plug: 12/16/2004 3:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/16/2004 6:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Ran tubing to 2500'.
Circulated 4 1/2" with 175 sxs 60/40 pozmix - 10% gel cement with 500# hulls.
Tied onto casing - pumped 30 sxs cement.
Max. P.S.I. 300#. S.I.P. 150#.
Pumped 30 sxs down backside.
Max. P.S.I. 400#. S.I.P. 100#.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

100

Signed Case Morris
(TECHNICIAN)

INVOICED
DATE 12-22-04
INV NO 2005060963


DEC 17 2004

F&B INVESTMENTS
 P.O. BOX 366
 RUSSELL, KS 67665
 CONTR REVLIN DRILLING CO CTY RUSSELL

8-14-13W
 C E/2 SW SE

GEOL FRANCIS WHISLER FIELD HALL-GURNEY

E 1868 KG CM 10/1/80 CARD ISSUED 1/29/81 IP P 10 BOPD
 1863 GL TARK 2401-34 OA
 API 15-167-21,543



SMP	TOPS	DEPTH	DATUM
GR HAV		2391	- 523
TARK SD		2400	- 532
DOVER		2416	- 548
LANG		2418	- 550
TARK LM		2457	- 589
WILL SD		2480	- 612
ELM		2525	- 657
TOP		2733	- 865
HEEB		2970	-1102
TOR		2990	-1122
DOUG		3003	-1135
LKC		3034	-1166
B KC		3301	-1433
CONG		3326	-1458
RTD		3368	-1500
NO LOG			

8-5/8" 200, 4 1/2" 2550
 DST (1) 2395-2450 (TARK)/15-60-45-45,
 REC 486' MW, SIP 911-488#, FP 173-
 193/203-264#
 MICT - CO, PF (TARK) 12/2401-04, 8/
 2406-08, 20/2423-28, 16/2430-34, FRAC'D
 (AMT NA), POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

WPA 486
 07/26
 MADIGEN