

6 030649

317

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-039-20,379-00-00

NEEUSE SEC. 25, T 5 S, R 30 W

2310 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name DAVIS "E" Well # 2

Operator: CITIES SERVICE OIL & GAS CORP.

County DECATUR 135.20

Name & Address 3545 NW 58TH STREET

Well Total Depth 4160 feet

OKLAHOMA CITY OK.

Conductor Pipe: Size _____ feet

73112

Surface Casing: Size 8 5/8 feet 278

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor HALLIBURTON License Number _____

Address OBERLIN KANSAS 67749

Company to plug at: Hour: PM Day: 22 Month: 1 Year: 19 86

Plugging proposal received from RICK BROWER

(company name) CITIES SERVICE (phone) _____

were: NO PIPE RECOVERED ORDER 350SX. 60/40POZ 24SX. GEL. 4SX. HULLS. HALIBURTON CMT. CO. LA RUE WATER TRUCKS 8 5/8 @ 278 w/ 225 5 1/2 @ 4155 w/ 200 DU @ 2600 w/ 460

Plugging Proposal Received by Carl Goodnow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30PM Day: 22 Month: 1 Year: 19 86

ACTUAL PLUGGING REPORT SPOT WITH TUBING @ 4160 2SX. HULLS 70SX. CMT. + 2SX. HULLS TO 3460 SPOT 18SX. GEL. TO 1985 SPOT 100SX. CMT. TO 974 SPOT 6SX. GEL. TO 495 SPOT 60SX. CMT. TIE ON TO 5 1/2 SQUEEZE w/ 5SX. CMT. MAX PSI 300# HELD CLOSE IN. PUMP DOWN 8 5/8 ANNULUS 90SX. CMT MIX. MAX. PSI 150 HELD CLOSE IN. PLUG COMPLETE

Remarks: _____

INVOICED

(if additional description is necessary, use BACK of this form.)

DATE FEB 6 1986

INV. NO. 12400

RECEIVED STATE CORPORATION COMMISSION FEB 3 1986 02-03-1986 CONSERVATION DIVISION

Signed Carl Goodnow (TECHNICIAN)

12 1-31-86