

6 030629

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-039-20,359-00-00

NE SE, SEC. 25, T. 5 S, R. 30 W

1980 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name DAVIS Well # "E" 1

Operator: CITIES SERVICE OIL & GAS CORP.

County DECATUR 147.06

Name & Address 2707 VINE STREET STE. 17

Well Total Depth 4525 feet

HAYS, KS.

Conductor Pipe: Size _____ feet

67601

Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING License Number 6050

Address CHASE KANSAS

Company to plug at: Hour: AM Day: 27 Month: 12 Year: 19 85

Plugging proposal received from MIKE KELSO

(company name) KELSO CASING (phone) _____

were: 8 5/8 @ 258 w/175 sx. 5 1/2 @ 4154 w/650 sx. PERFS, 3941 -> 4097'

ORDER COM. CMT & SAND SHOOT & RECOVER PIPE. ORDER 180 SX. 60# OP. OZ.

6 GEL 3% CC. 40 SX. GEL. 4 SX. HULLS. HALLIBURTON CMT. CO. HARUE

WATER TRUCKS.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 AM Day: 27 Month: 12 Year: 19 85

ACTUAL PLUGGING REPORT 5 SX. COM CMT ON BOTTOM w/BAILER. DUMP SAND TO 3900'

SPOT 5 SX COM. AMT. ON SAND w/BAILER. SHOT & RECOVERED 1500'

MIX. & PUMP 3 SX. HULLS 10 SX GEL. 100 SX. CMT MIX. + 1 SX. HULLS 30 SX GEL

8 5/8 W.P. 80 SX. CMT. MIX. MAX. PSI 450# CLOSE IN 300# PSI.

PLUG COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: _____
(if additional description is necessary, use BACK of this report)

JAN 8 1986
01-08-1986
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(if did not observe this plugging.

Signed Carl Goodrow
(TECHNICIAN)

63
1-6-85
MPS

DATE JAN 10 1986

INV. NO. 11888