

11-1
4- 031610

1932

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-039-20,879-00-00

E2 NW NW 1/4 SEC. 33, 05 S, 30 W
4620 feet from S section line
4290 feet from E section line

Operator license# 5422 Lease Middy well # 1

Operator: Abercrombie Drilling Co. County Decatur 135.42

Address: 150 N. Main Well total depth 4167 feet
Suite 801 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 216 feet

Aband. oil well __, Gas well __, Input well __, SWD __, D & A X

Plugging contractor: Abercrombie RTD, Inc. License# 30684

Address: 150 N. Main - Suite 801 - Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 1 Month: November Year: 91

Plugging proposal received from: Harold Maley

Company: Abercrombie Drilling Co. Phone: _____

Were: 8 5/8" set @ 216' w/160 sx. Condition hole. Balance plugs
and keep hole full with no less than 36 vis. mud. Order 190
60/40 pozmix - 6% gel. - 3% c.c. 8 5/8" W.P. Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 5:00P.M. Day: 1 Month: November Year: 91

Actual plugging report:

Spot plugs with drill pipe with 25 sx. @ 2650'.
100 sx. @ 1800' with hulls.
40 sx. @ 260'.
10 sx. @ 40' with W.P. STATE CORPORATION COMMISSION
Circulate 15 sx. in Rathole.

Remarks: Anhy. 2613' - 51' - Elevation 2896'. CONSERVATION DIVISION
Wichita, Kansas

INVOICED [] observe the plugging. Carl Goodrow

DATE 12-6-91
INV. NO. 34030

Lib.S.

(agent)
Form CP-2/3

RECEIVED
12-02-1991
DEC 02 1991