

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-20386-00-00

Spot: NWNE

Sec/Twnshp/Rge: 23-31S-14W

660 feet from N Section Line,

1980 feet from E Section Line

Lease Name: LAKE

Well #: 1

County: BARBER

Total Vertical Depth: 4590 feet

Operator License No.: 5339

Op Name: BERGMAN OIL CO., L.C.

Address: 150 N. MAIN, STE 520
WICHITA, KS 67202

PROD Size: 5.5 feet: 4588 WITH 350 SX CMT

SURF Size: 13.38 feet: 225 WITH 200 SX CMT

4149¹⁸

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 10/13/2004 3:15 PM

Plug Co. License No.: 31529

Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS

Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND 50' ABOVE PERFS WITH 5 SX CMT. PLUG AT 650' IWHT 12 SX GEL & 50 SX CMT. PLUG AT 250' WITH 80 SX CMT. PLUG AT 40' WITH 25 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 10/13/2004 4:30 PM

KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 2778'. CHECK PBTD PRIOR TO SANDING BACK. FOUND AT 2800'. SANDED BACK TO 2680' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 650' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 250' WITH 80 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.

Perfs:


Top	Bot	Thru	Comments
2735	2737		

RECEIVED
OCT 18 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2238' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

DATE 1-26-05
INV. NO. 2005061110

Form CP-2/3