

6 070375

API NUMBER 15-163-01300-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SE-NE-NW, SEC. 12, T. #6 S, R. 18 E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 7591
Operator: MARYLIN CHENSEY
Name & Address: 201 WEST 34th ST.
HAYS, KANSAS.
67601

_____ feet from S section line
_____ feet from E section line
Lease Name FAUBIAN Well # 1
County ROCKS 104.00
Well Total Depth 3300 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 269

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor HALLIBURTON CEMENTING Co License Number _____

Address EAST HWY 40 HAYS, KANSAS, 67601

Company to plug at: Hour: 9:30 AM Day: 22 ND Month: JULY Year: 19 85

Plugging proposal received from DEAN WEINLAND

(company name) KRUGER OIL COMPANY (phone) 913-628-3616

were: 8 5/8" - 269 FT SP. OUL #/NA. 5 1/2" CSG. SET @ 3300 FT #/NA.

PBTD. 3300 PERFS 3160-65 3240 3215-50 3245, DAKOTA ONMPEP IN SAND, BOTTOM

APPROX. 400 FT SHUT OFF WITH SAND. - TRAD CASING @ 900 TO 1100 FT, EIV. 1906' ANH. 1368'

ORDER 500 1/40 FORMIX GEL - CA-CL, 6 HULL'S, 4 5/8" FLAME AND 5 1/2" PLUG

RUN HALLIBURTON LINE TO SPOT SAND, SPOT CMT WITH TUBING, LOAD AND SQUEEZE

ANNULUS WITH CEMENT Plugging Proposal Received by Marylin Chensey
(DOIC (TECHNICIAN))

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:30 PM Day: 22 ND Month: JULY Year: 19 85

ACTUAL PLUGGING REPORT ORDERED 500 1/40 FORMIX GEL - CA-CL - 4 5/8" FLAME - 6 HULL'S + PLUG.

1 RAN HALLIBURTON LINE TAG BOTTOM AT 2718 FT, RAN 2 3/8" TUBING TO

2694 FT SPOTTED 50 CMT 1/4 FLAME, PULLED TUBING TO 2201 FT SPOTTED

100 CMT 1/4 FLAME 1/4 HULL'S, PULLED TUBING TO 1206 FT SPOTTED 100 CMT 1/4 FLAME

AND 1/4 HULL'S, PULLED TUBING TO 300 FT SPOTTED 1/50 CMT 1/4 HULL'S,

IN 5 1/2" CSG SQUEEZED IN 40 CMT, IN ANNULUS PUMPED IN 1/160 CMT.

Remarks: 1/2 HULL'S MIXED IN MAX. PS. 9 225. (CMT BY HALLIBURTON CMT.)

Returned on -7-18-85
I (did / did not) observe this plugging. STATE CORPORATION COMMISSION

Filled Both 5 1/2" + 8 5/8"
or Redi-Mix. 1 DATE 8-7-85

Total _____
INV. NO. 9384 RECEIVED
Conservation Division
Wichita, Kansas 8-5-85 FORM CP-2/3
Rev. 01-84