

4-070987

1-17 191 R

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-23,191 -00-00
Approx. S2 SE SW /4 SEC. 01, 06 S, 18 W
330 feet from S section line
2140 feet from E section line

Operator license# 30269 Lease Sigwing well # 1

Operator: Argent Energy, Inc. County Rooks 107.28

Address: 110 South Main Well total depth 3301 feet
Suite 510 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202-3745 Surface pipe 8 5/8 Inch @ 222 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Shields Drilling Company, Inc. License# 5655

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 17 Month: January Year: 92

Plugging proposal received from: Burton Berry

Company: Shields Drilling Co. Inc. Phone: 913-483-3141

Were: 8 5/8" - 223' S.P. cwc. w/150 sx. - 60/40 pozmix - 2% gel. -
3% c.c. By Allied Cement.K.C. Well. Elv. 1882'. Anhy. 1291'. No cir.
problems. Mud condition 44 vis. - 9.6 wt. - 10.2 wt. Proposal 200 sx. -
60/40 pozmix - 6% gel. - 3% c.c. optional and 1 sx. flocele. Spot with
drill stem, heavy mud between all plugs. No ar buckle. 25 sx. @ 1300' -
100 sx. w/1 sx.F.C. @ 780' - 40 sx. @ 273' - 10 sx. @ 40' - 15 sx. in
rathole - 10 sx. mousehole.

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 4:30P.M., Day: 17, Month: January, Year: 1992

Actual plugging report: Shields ordered 200 sx. 60/40 pozmix - 6% gel -
1 sx. flocele. Spotted and displaced with drill stem, with heavy mud
between all plugs.

1st. plug @ 1300' w/25 sx. cement.
2nd. plug @ 780' w/100 sx. cement w/1 sx. flocele.
3rd. plug @ 273' w/40 sx. cement.
4th. plug @ 40' w/10 sx. cement.
15 sx. in rathole (circulate) 10 sx. in mousehole (circulate)

Remarks: Cemented by Allied Cement.

Condition of casing(in hole):GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES NO
Plugged through TUBING , CASING . Elevation: 1882

I did / did not X observe the plugging.

DATE 3-11-92
INV. NO. 34725

Marion J. Schmidt
(agent)

RECEIVED - CONSERVATION DIVISION
Wichita, Kansas
MAR - 5 1992
3-5-92