

6 040295

API NUMBER 15-163-22.573-06-00 **R**

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NW NW, SEC. 26, T 6 S, R 18 W/E **XX**

4950 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9747

Lease Name Sander Well # 1-26

Operator: Universal Resources Corporation

County Rooks 118.30

Name & Address 1125 17th Street, Suite 1800

Well Total Depth 3640 feet

Denver, Co. 80202

Conductor Pipe: Size 0 feet

Surface Casing: Size 8⁵/₈ feet 247 w/165 sks

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A **XXX**

Other well as hereinafter indicated _____

Plugging Contractor Buffalo Drilling Co License Number 5143

Address Wichita, Ks.

Company to plug at: Hour: PM Day: 4 Month: December Year: 1984

Plugging proposal received from Merlin Glover

(company name) Buffalo Drilling (phone) _____

were: Order 200 sks 50/50 pozmix 6% gel 3% cal. cl., 1 sk hulls and 8⁵/₈" plug
Spot with drill pipe with no less than 36 vis. mud between all plugs, with good
circulation and no fluid loss.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None **XX**

Operations Completed: Hour: 1:30PM Day: 4 Month: December Year: 1984

ACTUAL PLUGGING REPORT

1st plug @ 1480 w/40 sks

2nd plug @ 875 w/100 sks w/2 sks hulls

3rd plug @ 260 w/40 sks

4th plug @ 40 w/10 sks (solid bridge)

10 sks in Rat Hole

Remarks: _____
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 2-14-85

INV. NO. 6965

Signed Dennis L. Hamel
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION

FEB 14 1985

CONSERVATION DIVISION 2-11-85
Wichita, Kansas