

8-10

6-050119

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-163-23,230 ⁰⁰⁻⁰⁰
S2 SW SW /4 SEC. 33, 6 S, 18 W
330 feet from S section line
4620 feet from E section line

Operator license# 6111 Lease J. L. Sander well # 1

Operator: N-B Company, Inc. County Rooks

Address: P. O. Box 506 Well total depth 3580 feet ^{116.35}
Russell, KS 67665 Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 240 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Emphasis Oil Operations License# 8241

Address: Russell, Kansas

Company to plug at: Hour: 9:00 pm Day: 10 Month: August Year: 1993

Plugging proposal received from: Jack Fox

Company: Emphasis Oil Operations phone: 913-483-5345

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

- 1st plug @ 3404 feet with 20 sacks Rat hole: 15 sacks
- 2nd plug @ 1470 feet " 25 " Mousehole: sacks
- 3rd plug @ 830 feet " 100 "
- 4th plug @ 290 feet " 40 "

5th plug @ 40 feet " wiper plug & 10sx
Plugging Proposal Received by: Bruce D. Basye
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 9:00 pm, Day: 10, Month: August, Year: 1993

Actual plugging report: Hole reported plugged as above.
Order 210 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 1970 GL, Anhydrite depth: 1493 - 1485 feet

Did penetrate Arbuckle, cemented by

I did / did not X observe the plugging

RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KANSAS
AUG 30 1993
CONSERVATION DIVISION
WICHITA, KANSAS

8-30-93

Bruce D. Basye
Bruce D. Basye Geologist
(agent)

Form CP-2/3

INVOICED
SEP 02 1993

DATE

INV. NO. 38526

HO