

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-163-22, 121-00-00

W-E-S-E, SEC 32, T 6 S, R 18 W E
3300 660 FEET FROM N(S) SECTION LINE

TECHNICIAN'S PLUGGING REPORT

330 FEET FROM W(E) SECTION LINE

OPERATOR LICENSE # 6725

LEASE NAME R. SANDERS Well # "A"-221

OPERATOR: ERIC WADDELL CO.
NAME & ADDRESS P.O. BOX 349
NATOMA, KANSAS.
67651

COUNTY ROOHS \$ 115.70

WELL TOTAL DEPTH 3560 FEET

CONDUCTOR PIPE: SIZE 0 FEET

SURFACE CASING: SIZE 8 5/8 FEET 207

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A X

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR LABANCO DRILLING, INC TAG. 458 LICENSE NUMBER 5980

ADDRESS BOX 289 NATOMA, MS.

COMPANY TO PLUG AT: HOUR: 7:30 AM DAY: 22 ND MONTH: AUG. YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM JOHN WEIS

(COMPANY NAME) LABANCO DRILLING, INC. (PHONE) 913-885-4497

WERE: 8 5/8" - 207 FT SP. CUL #130 ST QUICK SET (BY ALLIED CMT)

ORDER, 200 ST 50/50 FORMIX 6% GEL-3% CA-CL. AND 8 5/8" PLUG.

SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS

ARBuckle @ 3552 FT -> ELV. 1970 FT MINN. 1495'

PLUGGING PROPOSAL RECEIVED BY Marian Schmitt
(TECHNICIAN) DOIC

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE X

OPERATIONS COMPLETED: HOUR: 7:30 AM DAY: 22 ND MONTH: AUG. YEAR: 19 83

ACTUAL PLUGGING REPORT

ORDERED 200 ST 50/50 FORMIX 6% GEL-3% CA-CL. AND 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS

1st Plug @ 3540 FT #20 ST CMT., 2nd Plug @ 1500 FT #20 ST CMT.

3rd Plug @ 870 FT #100 ST CMT., 4th Plug @ 240 FT #40 ST CMT.

5th Plug ^{SOLID BRIDGE} HULL'S - PLUG @ 40 FT #10 ST CMT., 10 ST IN RAT HOLE (CIRCUING)

REMARKS: CEMENTED BY ALLIED CMT.

RECEIVED
STATE CORPORATION COMMISSION
AUG 29 1983 8-29-83

I (~~did~~ / DID NOT) OBSERVE THIS PLUGGING.

CONSERVATION DIVISION
Wichita, Kansas

SIGNED Marian Schmitt
(TECHNICIAN) DOIC

INVOICED
DATE 8-31-83
INV. NO. 5393-6