

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 163-21, 804-00-00

SW-SW-NE, Sec. 31, T 6 S, R 18 W/E

_____ feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

_____ feet from W/E section line

Operator License # 5131

Lease Name EHDS. Well # 1

Operator: THUNDERBIRD DRIG.
Name &
Address BOX 18407
WICHITA, KANS.
67212

County ROOFS

Well Total Depth 3603 feet

Conductor Pipe: Size - feet -

Surface Casing: Size 8 5/8" feet 371

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor THUNDERBIRD DRIG. License Number 28

Address BOX 18407 WICHITA, KS. 67212

Company to plug at: Hour: 1:00 PM Day: 15th Month: OCT Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO ED COOK.

(company name) THUNDERBIRD DRILLING INC (phone) 316-793-9011

were: 8 5/8" - 371 FE SP. CUL. w/225ST COMMON-2% GEL-2% CA-CL. (ALLIED)

ORDER 200ST 50/50 FORMIX 6% GEL-3% CA-CL. AND 8 5/8" PLUG.

SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1ST PLUG @ 3420 FE w/20ST CNT. -> 2ND PLUG @ 1530 FE w/20ST CNT.

3RD PLUG @ 870 FE w/100ST CNT. 4TH PLUG @ 390 FE w/40ST CNT.

5TH PLUG. ^{Solid Bridge} HULLS - PLUG @ 40 FE to 0 w/10ST CNT. signed

10ST IN RAT HOLE (CIRCULATE)

(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:30 PM Day: 15th Month: OCT Year: 19 82

ACTUAL PLUGGING REPORT 8 5/8" - 371 FE SP. CUL w/225ST CNT. (BY ALLIED)

ORDERED 200ST 50/50 FORMIX 4% GEL-3% CA-CL. AND 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1ST PLUG @ 3420 FE w/20ST CNT. -> 2ND PLUG @ 1530 FE w/20ST CNT.

3RD PLUG @ 870 FE w/100ST CNT. -> 4TH PLUG @ 390 FE w/40ST CNT.

5TH PLUG. ^{SOLID BRIDGE} HULLS - PLUG @ 40 FE to 0 w/10ST CNT. -> 10ST IN RAT HOLE (CIRCULATE)

Remarks: CEMENTED BY ALLIED CNT.

RECEIVED
STATE CORPORATION COMMISSION

OCT 26 1982
10-26-82

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were CONFERRED herein stated and that I (did / did not) observe this plugging.

INVOICED

DATE 11-15-82

INV. NO. 1666-W

Signed Marian Schmidt
(TECHNICIAN)