

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6926

Operator: Advantage Resources
Name & Address: 1600 Broadway
Suite 1940
Denver, Colorado

6-8-88
API NUMBER 15- 163-23-000-00-00
NW SW SE, SEC. 29, T. 6 S, R. 18 (W) E
_____ feet from S section line
_____ feet from E section line
Lease Name Ray Sanders Well # 1
County Rooks 117.16
Well Total Depth 3605 feet
Conductor Pipe: Size _____ feet
Surface Casing: SBz 5/8 feet 261

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling License Number 6033

Address 250 N. Water Suite 300 Wichita, Ks.

Company to plug at: Hour: _____ AM Day: 7 Month: June Year: 19 88

Plugging proposal received from Rod Farr

(company name) Murfin Drilling (phone) _____

were: Order 220 sx 60/40 pozmix-6% gel- 3% Cal. Cl, 1sk flocele and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Plugging Proposal Received by Bruce Basye
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None x

Operations Completed: Hour: 10:30AM Day: 8 Month: June Year: 19 88

ACTUAL PLUGGING REPORT 1st plug @ 3550' w/ 20 sx.

2nd plug @ 1520' w/ 20 sx.

3rd plug @ 900' w/ 100 sx. 1 sck flocele

4th plug @ 300' w/ 40 sx.

5th plug @ 40' w/ 10 sx.

15 sx in rat hole. 15 sx in mouse hole.

Remarks: Cemented by Allied
(If additional description is necessary, use BACK of this form.)

INVOICED (If not observe this plugging.)

DATE 7-26-88

Signed Bruce D Basye
(TECHNICIAN)

INV. NO. 21643 AUG 3 1988

Bruce D. Basye

STATE CORPORATION COMMISSION

JUL 20 1988 7-20-88

CONSERVATION DIVISION
Wichita, Kansas

D