

4-010779

S-4  
15-147-00624-00-00  
API number: ~~15-147-97-507~~

212  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW NW SW /4 SEC. 23 , 05 S, 20 W  
1650 feet from S section line  
4950 feet from E section line

Operator license# 5447

Lease Brown well # B-4

Operator: OXY USA, Inc.

County Phillips

Address: 110 S. Main  
#800  
Wichita, Kansas 67202

Well total depth 3605 feet 117.16  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 187 feet

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: OXY USA, Inc. License# 5447

Address: 110 S. Main, #800, Wichita, Kansas 67202

Company to plug at: Hour: 8:00A.M. Day: 4 Month: May Year: 92

Plugging proposal received from: Jim Nowel

Company: OXY USA, Inc. Phone:                     

Were: Order 400 sx. cement - 65/35 pozmix - 8% gel. - 500# hulls.  
Perf. anhydrite @ 1690' . Perf. base Dakota @ 1045'.  
5 1/2" @ 3563' . Perf. @ 3283' - 3559' . Elev. 2154'.

Plugging Proposal Received by: Dale F. Balthazor  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 11:30A.M., Day: 4, Month: May, Year: 92

Actual plugging report: Ran tubing to 3375', pumped down 100 sx. cement w/100# hulls. Pulled 1200' tubing, pumped down 100 sx. cement w/100# hulls. Pulled 1200' tubing, pumped down 50 sx. cement w/ 50# hulls. Circulated cement. Pulled tubing, pumped down casing 50 sx. cement 800# max. pressure, closed w/300# pressure. Holding. Pumped down 8 5/8" 100 sx. cement w/150# hulls. Max. pressure 700#. Closed w/300#. Holding.

Remarks: Halliburton Cement Company

Condition of casing(in hole): GOOD     BAD     Anhy. plug: YES     NO    

Bottom plug(in place): YES    , CALC    , NO     Dakota plug: YES     NO    

Plugged through TUBING    , CASING    . Elevation:                     

I did[     ], did not[     ] observe the plugging.

**INVOICED**

DATE 6-5-92

REV. NO. 35420

JUL 08 1992

Dale F. Balthazor  
MAY 18 1992

(agent)

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

5-18-92