


15-163-19064-0600

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rooks County. Sec. 3 Twp. 6 Rge. 18 (E) (W)
Location as "NE/CNW/SW" or footage from lines SE NW NW
Lease Owner PM Oil Enterprises
Lease Name Miller Well No. 2
Office Address Lakewood Office Bldg. 7580 W. 16th Denver, Colo.
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed 12-29 1956
Application for plugging filed 12-29 1956
Application for plugging approved 12-29 1956
Plugging commenced 10:00 P.M. 10-29 1956
Plugging completed 12:00 P.M. 10-29 1956
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Elton Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3620 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface pipe		-0-	200	8 5/8	200	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole to 190' with heavy rotary mud.
Set plug at 190' with 1/3 sacks hulls on top of plug.
Mixed 15 sacks cement on bottom plug.
Filled hole to 35' with heavy rotary mud.
Set plug at 35' with 1/3 sack hulls.
Hung on 2 wires and 10 sacks cement on top of plug.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor A. L. Jackson Drilling Company
Address Box 194 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
~~WXXXXXXXXXX~~ Dick B. Evans (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dick B. Evans
Box 194 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of January, 19 56

My commission expires 4-27-57

Virgil E. Huff
Notary Public.

PLUGGING
FILE SEC 3 T 6 R 18 W
BOOK PAGE 130 LINE 29

RECEIVED
STATE CORPORATION COMMISSION
1-16-57
JAN 17 1957
CONSERVATION DIVISION
Wichita, Kansas

15-163-19064-0000

Well Log
Miller #2
SE NW NW ~~3-16-18~~ 3-6-18W
Rooks County, Kansas

0	-	130	Surface dirt, sand and shells
130	-	200	Sand and shells
200	-	690	Shale and shells
690	-	935	Sand, shale and shells
935	-	1025	Shale
1025	-	1150	Sand and shale
1150	-	1450	Shale and red bed
1450	-	1485	Anhydrite
1485	-	1545	Shale
1545	-	2070	Shale & shells
2070	-	2210	Lime and shale
2210	-	2335	Lime
2335	-	2585	Lime and shale
2585	-	2695	Shale & lime streaks
2695	-	2995	Lime & shale
2995	-	3185	Lime
3185	-	3245	Lime - Kansas City
3245	-	3495	Lime
3495	-	3526	Lime - conglomerate
3526	-	3549	Simpson Dol.
3549	-	3590	Shale & cherty lime
3590	-	3620	Con. - Arbuckle
3620			T.D.

State of Kansas
County of Barton SS

Dick B. Evans, accountant for A. L. Jackson Drilling Company, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above described well as filed and that the same are true and correct.

Dick B. Evans
Dick B. Evans

Subscribed and sworn before me this 10 day of JANUARY, 1957

Virgil E. Belford, Jr.
Virgil E. Belford, Jr.
Notary Public Barton County

My commission expires: April 27, 1957

PLUGGING			
FILE	SEC	<u>3</u>	<u>6</u> <u>18W</u>
		<u>21</u>	<u>21</u> <u>R 11W</u>
BOOK	PAGE	<u>132</u>	LI F <u>20</u>
		<u>136</u>	<u>29</u>

RECEIVED
STATE CORPORATION COMMISSION
1-14-57
JAN 14 1957
CONSERVATION DIVISION
Wichita, Kansas