

API NUMBER 15-163-23,191-00-00

LEASE NAME Sigwing

WELL NUMBER 1

330 Ft. from S Section Line

2,140 Ft. from ^W~~S~~ Section Line

SEC. 1 TWP. 6 RGE. 18 (~~X~~or(W))

COUNTY Rooks

Date Well Completed 1-17-92

Plugging Commenced 1-17-92

Plugging Completed 1-17-92

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Argent Energy, Inc.

ADDRESS 110 South Main, Suite 510, Wichita, KS.

67202

PHONE#(316) 262-5111 OPERATORS LICENSE NO. 30269

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-17-92 (date)

by Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3,301'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	223'	Cmtd. w/150 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Push plug to 1,300', spot 25 sax cement on plug thru drill pipe. Push bridge plug to 780', spot 100 sax cement on plug thru drill pipe. Push bridge plug to 273', spot 40 sax cement on plug. Push bridge plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole. Cement is 60/40 pozmix w/6% gel and 3% calcium chloride.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 164

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ARGENT ENERGY, INC. 1103 04 1992 24-92

STATE OF KANSAS COUNTY OF RUSSELL

Jack P. Beeman, Sec.-Treas. (Employee of Contractor or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Shields Drilling Co. Jack P. Beeman, Sec - Treas.

(Address) Shields Bldg., Russell, KS. 67665

SUBSCRIBED AND SWORN TO before me this 30th day of January, 19 92

Ruth Phillips
 Notary Public

My Commission Expires: _____

