

15-163-20094-00-00

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County, Sec. 16 Twp. 6 Rge. 18 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines NW NW NW

Lease Owner Leo J. Dreiling Oil Company

Lease Name McQueen Well No. 1

Office Address Route 2, Victoria, Kansas 67671

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed 1-29- 19 68

Application for plugging filed 12-22 19 69

Application for plugging approved 12-23 19 69


Plugging commenced 1-2 19 70

Plugging completed 1-2 19 70

Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 11 19 68

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Casing				5 1/2"		1984'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged down 8 5/8" casing with 4 sacks hulls, 20 sacks gel followed with 70 sacks cement, 1/2 sacks hulls, 8 sacks gel and 60 sacks cement. Input pressure 200# and shut in pressure 200#. Sun Cementing did the plugging.

RECEIVED
STATE CORPORATION COMMISSION
FEB 2 1970
CONSERVATION DIVISION
Wichita, Kansas
2-2-70

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Russ Casing Pulling, Inc.

Address P. O. Box 1082, Great Bend, Kansas 67530


STATE OF KANSAS, COUNTY OF ELLIS, ss.

I, Leo F. Dreiling (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling

LEO F. DREILING, ROUTE 2, VICTORIA, KANSAS 67671 (Address)

SUBSCRIBED AND SWORN to before me this 30th day of January, 19 70



Joseph A. Hess Notary Public.

My commission expires September 19, 1970

15-163-20094-00-00

L. J. DREILING and SONS, Inc.
VICTORIA, KANSAS

WELL LOG

Company Leo J. Dreiling Oil Company
Route 2
Victoria, Kansas
Farm McQueen No. 1
Total Depth 3572'
Comm. 1-24-68 Comp. 1-29-68

Sec. 16 Twp. 6 Rng. 18
Location NW-NW-NW
County Rooks
Elevation: 1971' K.B.
1968' D.F.
1966' G.R.

Contractor L. J. Dreiling & Sons, Inc.
Route 2
Victoria, Kansas
Casing Record
174' - 8 5/8"
3572' - 5 1/2"

Cement Record
125 sacks cement
150 sacks cement
10% salt saturated

Production:

Figures Indicate Bottom of Formations

0'	40'	Top Soil & Clay
40'	160'	Shale & Rock
160'	174'	Blue Shale
174'	774'	Shale & Sand
774'	960'	Sand with streaks of Hard Sand
960'	1165'	Sand
1165'	1465'	Shale & Redbed
1465'	1472'	Anhy.
1472'	1499'	Anhy.
1499'	1757'	Shale
1757'	2020'	Shale & Shells
2020'	2465'	Shale & Shells
2465'	2630'	Shale & Lime
2630'	2995'	Shale & Lime
2995'	3145'	Lime & Shale
3145'	3280'	Lime & Shale
3280'	3370'	Lime
3370'	3441'	Lime
3441'	3510'	Lime
3510'	3525'	Lime
3525'	3572'	Lime
3572'	T.D.	

RECEIVED
CORPORATION COMMISSION
DEC 23 1969
CONSERVATION DIVISION
Wichita, Kansas
12 23-69

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your McQueen #1.

Leo F. Dreiling
LEO F. DREILING

Subscribed and sworn to before me this 30th day of January 1968.



Joseph A. Hess
JOSEPH A. HESS NOTARY PUBLIC

My commission expires: September 19, 1970