


15-163-20479-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217

Reeks County, Sec. 16 Twp. 6 Rge. 18 (E) (W)
SW NE SW



Locate well correctly on above
Section Plat

Location as "NE/CNWxSWx" or footage from lines _____
Lease Owner A. Scott Ritchie
Lease Name McQueen #1 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 9/3/74 _____ 19____
Plugging completed 9/5/74 _____ 19____
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Balthazer
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2575 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	208	none
				5 1/2"	3510	2578'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it to the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, pushed plug to 3320' and ran sand and 4 sacks cement.
Shot pipe at 2815', 2591', pulled 82 joints. Pumped 4 sacks hulls,
30 sacks gel and 120 sacks cement, 50-50 pos with 6% gel.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
OCT 24 1974
CONSERVATION DIVISION
Wichita, Kansas

10-24-74

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KELSO CASING PULLING
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of September, 19 74

MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

WELL LOG

15-163-20479-00-00

OPERATOR: A. SCOTT RITCHIE

WELL NAME: MC QUEEN #1 LOCATION: SW NE SW

COUNTY: ROOKS STATE: KANSAS

WELL COMMENCED: DEC 28 '72 WELL COMPLETED: JAN 6 '73

ELEVATION: 1983 KB TOTAL DEPTH: 3575'

PRODUCTION: PRODUCING RIG NO: 1

CASING - 8-5/8": SET @ 208.65 (5 JTS) 8 5/8" 28# W/150 SX CEM / 2% GEL
5-1/2": SET @ 3510.00' (113 JTS) USED 14# W/125 SX 60-40 / 3% CA CL
SALT SAT POZMIX

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	370	SHALE		
370	900	SHALE & SHELLS		
990	1200	SAND		
1200	1290	SHALE & RED BED		
1290	1510	SHALE & SAND		
1510	1551	ANHYDRITE		
1551	2125	SHALE	2 1/2 @ 1900'	
2125	3193	LIME & SHALE	1 1/2 @ 2485'	
3193	3520	LIME	1 @ 3230	DST #1 3204'-3270'
3520	3575	LIME & SHALE		DST #2 3270'-3300'
	3575	RTD		

RECEIVED
STATE CORPORATION COMMISSION
JUL 17 1974
CONSERVATION DIVISION
Wichita, Kansas
7-17-74

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By [Signature]

SUBSCRIBED AND SWORN TO, BEFORE ME, This 5th day of JANUARY, 1973.

EXP. DEC. 7, 1975

[Signature]
PHYLLIS BUCHANAN - NOTARY PUBLIC

