

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-163-21,907-0000

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE NAME Hamit

WELL NUMBER 1

SPOT LOCATION C SE NW SE

SEC. 2 TWP. 6 RGE. 20 ~~W~~ W

COUNTY Rooks

DATE WELL COMPLETED 02/01/83

PLUGGING COMMENCED 08/27/84

PLUGGING COMPLETED 08/27/84

LEASE OPERATOR CINCO ENERGY COMPANY

ADDRESS P. O. Box 3723 - Victoria, Texas 77903-3723

PHONE #(800) 531-3640 OPERATORS LICENSE NO. 8819

CHARACTER OF WELL OIL
(OIL) Gas, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? YES

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Hays, Kansas

Is ACC-1 FILED? YES IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION Regen Sand DEPTH TO TOP 3602' BOTTOM 3618' T.D. 3618'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Regen Sand	Oil	3602'	3618'	8 5/8"	272'	4'
				4 1/2"	3606'	4'

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Pumped 2 barrels of cement between 8 5/8" and 4 1/2", pressured up to 500 PSI, held for ten (10) minutes. Plugged 4 1/2" as follows: 3 sacks of Hulls, 3 sacks of Gel, 100 sacks of 50/50 Pozmix + 6% Gel + 3% CaCl₂. This well was an open hole completion with DV tool set at 1766'.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Halliburton Services LICENSE No. 5287
ADDRESS Oberlin, Kansas

STATE OF TEXAS COUNTY OF VICTORIA, ss.

BILL THETFORD (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) Bill Thetford
Bill Thetford/Authorized Agent
(ADDRESS) P. O. Box 3723-Victoria, TX 77903

SUBSCRIBED AND SWORN TO BEFORE ME THIS 24th DAY OF September, 19 84

Scott A. Powell
NOTARY PUBLIC

MY COMMISSION EXPIRES: 9-4-88

RECEIVED
STATE CORPORATION COMMISSION
9-28-84
SFP 28
FORM CP-4
REVISED 06-83
CONSERVATION DIVISION
Wichita, Kansas