

RECEIVED

SEP 16 2002  
9-16-2002  
KCC WICHITA

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-093-20012-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Geo. R. Shaw KCC LICENSE # 5062  
(owner/company name) (operator's)

ADDRESS 150 N. Main, Suite 1001 CITY Wichita

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (620) 275-7888

LEASE Smalley WELL# 1-34 SEC. 34 T. 24S R. 38 (East/West)

app- E2 SE - W2 - SE SPOT LOCATION/OOOO COUNTY Kearny  
KCC - 1-28-05 - SKA - Per CP2-3.

1320 FEET (in exact footage) FROM (S) N (circle one) LINE OF SECTION (NOT Lease Line)

1420 FEET (in exact footage) FROM (E) W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#           

CONDUCTOR CASING SIZE            SET AT            CEMENTED WITH            SACKS

SURFACE CASING SIZE 10.750" SET AT 217' CEMENTED WITH 225 SACKS

PRODUCTION CASING SIZE 7" SET AT 2380' CEMENTED WITH 200 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 5.5" slotted liner from 2367'-2471'

ELEVATION 3157' T.D. 2465' PSTD 2465' ANHYDRITE DEPTH 1880' - est.  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set a CIBP @ 2300' w/2sx cement on top, load casing w/water and pressure test, perforate 7" casing at 660', cement backside of 7" with cement and leave cement to surface inside 7". cement to be 60/40 Pozmix w/6% gel.  
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? N.A.  
If not explain why? none available

**PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.**

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Ron Osterbuhr PHONE# ( ) 620-275-7888

ADDRESS P.O. Box 1152 City/State Garden City, KS 67846

PLUGGING CONTRACTOR Will advise Halliburton Energy Service KCC LICENSE # 99997  
(company name) (contractor's)

ADDRESS 210 W. Park Ave. Ste 2000, Okc. Ok. 73102 PHONE # ( )           

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Will advise 12-12-02 Plugged

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 09/13/2002 AUTHORIZED OPERATOR/AGENT: Conrad Osterbuhr  
(signature)