

JAN 14 2002

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

FORM CP-1 (3/92)

CONSERVATION DIVISION

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-187-20965-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Mariah Energy, LLC KCC LICENSE # 32931 ^{10/02}
(owner/company name) (operator's)

ADDRESS 1776 Lincoln Street, Suite 1314 CITY Denver

STATE CO ZIP CODE 80203 CONTACT PHONE # (303) 770-1439

LEASE Roger Canny WELL# 1-1533 SEC. 33 T. 28S R. 40 (East/West)

NW SE SW SE SPOT LOCATION/QQQQ COUNTY Stanton

400 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

1700 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 1708' CEMENTED WITH 650 Lite SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 5636' CEMENTED WITH 200 .50/50 POZ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 5438-44; 5404-12'; 5388-96'; 5335-59' CIBP @ 5430'

ELEVATION 3290' T.D. 5660' PBSD 5430' ANHYDRITE DEPTH 1700'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING CIBP @ 5300' & cap w/25sx 60/40, cut 4 1/2" csg above

free pt at 4865 TOC, 100sx @ 3065'; 50 sx @ 1750', 40 sx @ 800', 10 sx @ 40',

Hole loaded w/mud. Per Kevin Strube 1/8/02.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Richard Gray-Presco Western, LLC PHONE# (303) 864-1881 x103

ADDRESS 1775 Sherman St, Ste. 2950 City/State Denver, CO 80203

PLUGGING CONTRACTOR Kerr Well Service, Inc. KCC LICENSE # 32722
(company name) (contractor's)

ADDRESS PO Box 184, Tyrone, OK 73951-0184 PHONE # ()

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 2-6-02 Plugged

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1/10/02 AUTHORIZED OPERATOR/AGENT: [Signature]
(signature)