

RECEIVED
MAY 21 2003
KCC WICHITA

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev.03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-035-21,831-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date. 6/03

WELL OPERATOR Range Oil Company, Inc. KCC LICENSE # 5120
ADDRESS 125 N. Market, Suite 1120 (owner/company name) CITY Wichita (operator's)

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 265-6231

LEASE Maddix WELL# 4 SEC. 11 T. 33 R. 5 (East ~~West~~)

- - NW - SW SPOT LOCATION/QQQQ COUNTY Cowley

1980 FEET (in exact footage) FROM (S) (circle one) LINE OF SECTION (NOT Lease Line)

660 FEET (in exact footage) FROM (W) (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# E-26,754

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8 SET AT 178 CEMENTED WITH 85 SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 3150 CEMENTED WITH 75 SACKS/bottom

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 3101 to 3128' / & 78 sx from 225' to surface

ELEVATION 1257 / 1264 T.D. 3150 PSTD _____ ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Bail 100' plug on bottom with 10 sacks cement. Add gel spacer to 1000'. Bail 50' plug at 1000' with 5 sacks cement. Add gel spacer to 250' Circulate cement from 250' to surface. The 4 1/2" casing is cemented in place and will not be removed.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No

If not explain why? Drilled in 1978. Scout card & KCC Enhanced Recovery Order is enclosed.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Alan Nation PHONE# () 620 - 221 - 6345

ADDRESS Strother Field, 7710 Ninth Ave. City/State Winfield, KS 67156

PLUGGING CONTRACTOR United Cementing & Acid Company, Inc. KCC LICENSE # 30437
2510 W. 6th, El Dorado KS 67042 (company name) (contractor's)

ADDRESS 125 N. Market, #1120 Wichita, KS 67202 PHONE # () 313 265 6231

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) A.S.A.P. 7-15-03 Plugged.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 5-20-03 AUTHORIZED OPERATOR/AGENT: John M. Washburn
(signature)