

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15-065-01774-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date ~~4/2/53~~ 3-16-53 ^{KCC} _{ap3}

2/05

Well Operator: Jolen Operating Company (Owner / Company Name) KCC License #: 31822 (Operator's)

Address: c/o Zinszer Oil Company, Inc., P.O. Box 211 City: Hays

State: Kansas Zip Code: 67601 Contact Phone: (785) 625-9448

Lease: Herrold Well #: 3 Sec. 25 Twp. 10 S. R. 21 East West

NW - SW - NW Spot Location / QQQQ County: Graham

~~4950~~ 3630 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

~~3630~~ 330 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 202' Cemented with: 150 Sacks

Production Casing Size: 5 1/2" Set at: 3717' Cemented with: 125 Sacks

List (ALL) Perforations and Bridgeplug Sets: Squeezed 250 sx cement @ 1050' (10/3/53), cement basket @ 1635'

Elevation: 2132' (G.L. / K.B.) T.D.: 3741 PBTD: 3741 Anhydrite Depth: 1620' (Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): as per Hays KCC

RECEIVED

JAN 28 2005

KCC WICHITA

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? old well

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Perry S. Henman

Phone: (785) 625-9448

Address: P.O. Box 211 City / State: Hays / Kansas

Plugging Contractor: Swift Services (Company Name) KCC License #: 32382 (Contractor's)

Address: Ness City, Kansas Phone: (785) 798-2300

Proposed Date and Hour of Plugging (if known?): mid February, weather permitting

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 1/24/05 Authorized Operator / Agent: [Signature] (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

10/05

DRILLER'S LOG

15-065-01774-00-00
 Company: Anderson-Fricker Oil Corp.

Farm: Herrold Well No.: 3

Total Depth: 3713'

Comm: 3-9-53 Comp.: 3-16-53
 Contractor: Glenn W Peel

Casing: 8 5/8" - 202' Cem.
 5 1/2" - 3710' Cem.

NW/4, SW/4, NW/4
 Sec. 24, Twp. 10S, Rge. 21W
 25
 County: Graham,
 Kansas

Elevation:

Production:

Figures below indicate bottom of formation:

Surface clay	0' -	202
Shale		1620
Anhydrite		1650
Shale		2200
Shale & Lime		2485
Lime		3080
Lime & Shale		3160
Lime		3275
Shale & Lime		3330
Lime		3713
Total Depth		3713

RECEIVED
 JAN 28 2005
 KCC WICHITA

This is to certify that the above information is, to the best of our knowledge, true and correct.

GLENN W. PEEL

BY: Wm Herbert

SUBSCRIBED AND SWORN TO BEFORE me this 18th day of March, 1953

My commission expires June 4, 1955

Marion M. Herbert
 Notary Public

Elevation	3132' RB	
Anhydrite	1620 (512)	Set 5 1/2" @ 3710' w/125 ax cem.
Topeka	3156 (-1024)	MICT and CO to RTD 3713'. Swab 1 1/2 BOPH/4 hrs..
Heebner	3360 (-1228)	DD to 3715'. Swab 1 1/2 BOPH/7 hrs.. Az. w/250 gal.
Toronto	3385 (-1253)	max. pres. 800#, min. press. 450#. Swab 3 BOPH/10 hrs.
Lansing	3403 (-1271)	RT & R. Pumped 63 BO, no water in 17 hrs., 10-34" SPM.
Simpson	3703 (-1571)	Pumped 72 BO, 2% water in 24 hrs., 10-34" SPM.
Arbuckle	3709 (-1577)	Final Report: pumped 66 BO, 0.2% water in 24 hrs. 10-34"
R.T.D.	3713 (-1581)	SPM.



NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Jolen Operating Company
100 N. Broadway, STE 2460
Oklahoma City, OK 73102

January 31, 2005

Re: HERROLD #3
API 15-065-01774-00-00
NWSWNW 25-10S-21W, 3630 FSL 330 FWL
GRAHAM COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550

Sincerely


David P. Williams
Production Supervisor