

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02973-00-00
Spot: NENESW Sec/Twnshp/Rge: 3-14S-17W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease Name: GOETZ C Well #: 1
County: ELLIS Total Vertical Depth: 3551 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

PROD Size: 5.5 feet: 3504 w/100 sxs cmt
SURF Size: 8.625 feet: 1068 w/375 sxs cmt

1115 41

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/18/2005 12:30 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: CURT GABEL Company: BEREXCO, INC. Phone: (785) 623-0546

Proposed Plugging Method: Ordered out 350 sxs 60/40 pozmix - 10% gel - 500# hulls.
Top of fish at 2234'. Rods and pump out tubing - stuck.
Dakota 256' - 556'. Anhy 1170' - 1210'. Salt 1547' 1832'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/18/2005 4:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perforated at 575' - 1200' - 1875'.
Ran tubing to 1900'.
Allied pumped 240 sxs 60/40 pozmix - 10% gel - circulated both 5 1/2" and 8 5/8".
PTOH. Allied pumped 35 sxs cement down 5 1/2" casing with 200# hulls.
Max. P.S.I. 900#. S.I.P. 400#.
Hooked up to 8 5/8" and pumped 75 sxs cement.
Max. P.S.I. 500#. S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
3504	3551	OH	

RECEIVED
JAN 26 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

INVOICED

DATE

1-28-05

INV. NO.

2005061117

Form CP-2/3

JAN 24 2005

_____ C. S. R.

MS C EN 3-14-17W

County _____

E 1986 Comm. 9-3-41 Comp. 9-22-41 IP 20 30 PM

Caseing
8" 1068
5" 705E

6009 0TH/30 hrs

Top	Depth	Datum
ANHY	1061	+ 925
TAMS	3268	
ARB	3504	
TD	3535	

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

