

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-19010-00-00

Spot: SWSNW

Sec/Twnshp/Rge: 12-17S-9W

2970 feet from S Section Line, 3630 feet from E Section Line

Lease Name: LORRAINE

Well #: 1-2

County: ELLSWORTH

Total Vertical Depth: 3260 feet

Operator License No.: 3273

CIBP Size: feet: 2870

Op Name: LOEB, HERMAN L.

CIBP Size: feet: 3024

Address: PO BOX 524

PROD Size: 4.5 feet: 3258

LAWRENCEVILLE, IL 62439

SURF Size: 8.625 feet: 192

A 105⁹⁵

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/27/2004 11:00 AM

Plug Co. License No.: 7023

Plug Co. Name: KLIMA WELL SERVICE, INC.

Proposal Rcvd. from: ALAN VRATIL

Company: KLIMA WELL SERVICE, INC.

Phone: (620) 886-3563

Proposed Plugging Method: CIBP @ 3024' & 2870'. Pump 35 sxs @ 2100'. Perf @ 1175', 850' & 242'. Run tubing to 1175' & pump 35 sxs, pull tubing to 850' & pump 35 sxs, pull tubing to 242' & circ cement to surf.

RECEIVED
KCC DISTRICT #2

JAN 7 - 2005

WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER

WitnessType: PARTIAL

Date/Time Plugging Completed: 12/28/2004 10:00 AM

KCC Agent: GREG EVES

Actual Plugging Report:

CIBP at 3024' and 2870'. Pumped 35 sacks of cement at 2100'; perforated at 1175', 850', and 242'. Ran tubing to 1175' and pumped 35 sacks of cement. Pulled tubing to 850' and pumped 35 sacks of cement. Pulled tubing and circulated cement to surface on 12/28/2004 after losing circulation on 12/27/2004.

60/40 posmix with 4% gel

Allied Cement #20607 & #20608

Perfs:

Top	Bot	Thru	Comments
3202	3206		
3047	3051		
2886	2892		
2430	2436		
2150	2160		

RECEIVED
JAN 28 2005
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

Greg Eves

(TECHNICIAN)

INVOICED

DATE

1-28-05

*INV. NO.

2005061124