

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-20259-00-00

Spot: Sec/Twnshp/Rge: 30-23S-17E
600 feet from S Section Line, 660 feet from E Section Line
Lease Name: R GEORGE Well #: 9
County: WOODSON Total Vertical Depth: 950 feet

Operator License No.: 32710
Op Name: LAYMON OIL II, LLC
Address: 1998 SQUIRREL RD
NEOSHO FALLS, KS 66758

PROD Size: 2 feet: 950
SURF Size: 7 feet: 40

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/19/2005 10:00 AM
Plug Co. License No.: 8469 Plug Co. Name: NICKELL, RALPH DBA NICKELL DRILLING
Proposal Rcvd. from: MIKE LAYMON Company: LAYMON OIL II, LLC Phone: (620) 963-2495

Proposed Plugging Method: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 950' THAT HAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE
Date/Time Plugging Completed: 01/19/2005 4:30 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

1" PIPE WAS RAN INTO THE 2" CASING TO 950'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 7" ANNULUS TO 475'. AT THAT DEPTH A SOLID OBSTRUCTION WAS ENCOUNTERED. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 7" SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED
KCC DISTRICT #3

JAN 26 2005 CPT

CHANUTE, KS

RECEIVED
JAN 28 2005
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

Clayton R. Titel

(TECHNICIAN)

INVOICED

DATE 1-28-05

INV. NO. 2005061123