

4-032120

API Number: 15-023-20,068-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

12-15

NE SW \_\_\_\_\_ / 4 SEC. 35 , 05 , 37 W  
1980 feet from S section line  
3300 feet from E section line

Operator license# 5393 Lease: Fisher Well # 3

Operator: A.L. Abercrombie, Inc. County: Cheyenne 162.60

Address: Rt. 1 - Box 56 Well total depth 5003 feet  
Great Bend, Kansas 67530 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 385 feet

Aband. oil well X, Gas well \_\_\_\_\_, Input well X, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Allied Cement Company License# \_\_\_\_\_

Address: Oakley, Kanas 67748

Company to plug at: Hour: A.M. Day: 15 Month: December Year: 1995

Plugging proposal received from: Bill Sowles

Company: A.L. Abercrombie, Inc. Phone: \_\_\_\_\_

Were: Order 200 sxs 60/40 pozmix - 10% gel - 300# hulls.  
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All [ ], Part [ ], None [ X ]

Completed: Hour: 11:00 A.M., Day: 15, Month: December, Year: 1995

Actual plugging report: 8 5/8" set at 385' cwc with 225 sxs. 4 1/2" set at 4097' with 200sxs. D.V. set at 3093' w/775 sxs cwc. Prod. Perf. 3614' - 4062'. P.B.T.D. 4075'. Pressured backside to Max. P.S.I. 500#. Held. Squeezed 4 1/2" with 200 sxs cement blend with 300# hulls mixed into Max. P.S.I. 300#. Held. Plug complete.

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD \_\_\_\_\_ BAD \_\_\_\_\_ Anhy.plug: YES \_\_\_\_\_ NO \_\_\_\_\_  
Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES \_\_\_\_\_, NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING \_\_\_\_\_ Elevation: \_\_\_\_\_ GL

INVOICED I did not [ X ] observe the plugging.

Carl Goodrow  
(agent)

DATE 1-5-96  
INV. NO. 44389