

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-113-20485-00-00  
Spot: SENWNW Sec/Twnshp/Rge: 25-19S-1W  
4320 feet from S Section Line, 4329 feet from E Section Line  
Lease Name: SCHMIDT Well #: 3  
County: MCPHERSON Total Vertical Depth: 2939 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N. MARKET, STE 710  
WICHITA, KS 67202

PROD Size: 4.5 feet: 2938 100 SX CMT  
SURF Size: 8.625 feet: 159 125 SX CMT

#95 52

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/02/2004 12:30 PM  
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION  
Proposal Rcvd. from: ALAN L DEGOOD Company: AMERICAN ENERGIES CORPORAT Phone: (316) 263-5785

Proposed Plugging Method: Sand to 2,850' & top with 4 sxs. cement. Rip casing loose & pull same. Run tubing to 425' & spot 35 sxs. cement. Pull tubing to 250' & circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: PARTIAL  
Date/Time Plugging Completed: 12/03/2004 3:30 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 2,840' & topped with 4 sxs. cement. Ripped casing loose @ 800' & pulled same. Ran tubing to 440' & spotted 2 yards slurry mix (50 sxs. cement). Pulled tubing to 244' & circulated 7 yards slurry mix (175 sxs. cement) to the surface.

Perfs:

Top	Bot	Thru	Comments
2904	2914		

RECEIVED  
KCC DISTRICT #2  
JAN 21 2005  
WICHITA, KS

RECEIVED  
JAN 28 2005  
KCC WICHITA

Remarks: USED SLURRY MIX BY HESSTON CONCRETE INC. INVOICE # 76980.

Plugged through: TBG

District: 02

Signed Michael Wilson  
(TECHNICIAN)

INVOICED  
DATE 1-28-05  
INV. NO. 2005061115