

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-01803-00-00

Spot: NWNWNW

Sec/Twnshp/Rge: 18-17S-10W

4950 feet from S Section Line, 4950 feet from E Section Line

Lease Name: KRAFT-PRUSA

Well #: 9-1

County: ELLSWORTH

Total Vertical Depth: 3263 feet

Operator License No.: 4058

Op Name: AMERICAN WARRIOR, INC.

Address: PO BOX 399

GARDEN CITY, KS 67846

PROD Size: 5.5 feet: 3248 85 SX CMT

SURF Size: 8.625 feet: 314 150 SX CMT

#106<sup>05</sup>

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 01/07/2005 3:00 PM

Plug Co. License No.: 6426

Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC

Proposal Rcvd. from: JODY SMITH

Company: AMERICAN WARRIOR, INC.

Phone: (620) 275-2963

Proposed  
Plugging  
Method:

See actual report.

RECEIVED  
KCC DISTRICT #2

JAN 10 2005

WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER

WitnessType: PARTIAL

Date/Time Plugging Completed: 01/07/2005 6:00 PM

KCC Agent: VIRGIL CLOTHIER

**Actual Plugging Report:**

Ran tubing; encountered obstructions at various places, i.e., 1067', 465', and 760'. Used power swivel and mud pump to finally get to 974'. Perforated at 950' and 365'. Ran tubing to 950' and pumped 70 sacks of cement with cotton hulls. Pulled tubing to 365' and circulated cement to surface. Pumped cement on backside of 5-1/2" to surface.

60/40 posmix with 4% gel.

Swift Services #7545

**Perfs:**

Top	Bot	Thru	Comments
3153	3156		

RECEIVED

JAN 28 2005

KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

INVOICED

DATE 1-28-05

INV. NO. 2005061116